0952412 PCT/GB98/03011

TENT COOPERATION TREATY

From the INTERNATIONAL BUREAU

PCT	To:
NOTIFICATION OF ELECTION (PCT Rule 61.2)	United States Patent and Trademark Office (Box PCT) Crystal Plaza 2 Washington, DC 20231
	ÉTATS-UNIS D'AMÉRIQUE
Date of mailing (day/month/year) 17 May 1999 (17.05.99)	in its capacity as elected Office
International application No. PCT/GB98/03011	Applicant's or agent's file reference 30960116 WO
International filing date (day/month/year) 08 October 1998 (08.10.98)	Priority date (day/month/year) 08 October 1997 (08.10.97)
Applicant BRYAN-BROWN, Guy, Peter et al	
Rule 32.2(b).	y Examining Authority on: (10.04.99)
The International Bureau of WIPO	Authorized officer

Facsimile No.: (41-22) 740.14.35

34, chemin des Colombettes 1211 Geneva 20, Switzerland C. Carrié

Telephone No.: (41-22) 338.83.38



PCT

NOTICE INFORMING THE APPLICANT OF THE **COMMUNICATION OF THE INTERNATIONAL APPLICATION TO THE DESIGNATED OFFICES**

(PCT Rule 47.1(c), first sentence)


To:

LAWRENCE, Richard, Anthony Hewlett-Packard Limited Intellectual Property Section

From the INTERNATIONAL BUREAU

Filton Road Stoke Gifford

Bristol BS34 8QZ ROYAUME-UNI



Date of mailing (day/month/year) 15 April 1999 (15.04.99)

Applicant's or agent's file reference

30960116 WO

IMPORTANT NOTICE

International application No. PCT/GB98/03011

International filing date (day/month/year) 08 October 1998 (08.10.98)

Priority date (day/month/year) 08 October 1997 (08.10.97)

Applicant

HEWLETT-PACKARD COMPANY et al

1. Notice is hereby given that the International Bureau has communicated, as provided in Article 20, the international application to the following designated Offices on the date indicated above as the date of mailing of this Notice: CN, EP, JP, KR, US

In accordance with Rule 47.1(c), third sentence, those Offices will accept the present Notice as conclusive evidence that the communication of the international application has duly taken place on the date of mailing indicated above and no copy of the international application is required to be furnished by the applicant to the designated Office(s).

2. The following designated Offices have waived the requirement for such a communication at this time:

SG

The communication will be made to those Offices only upon their request. Furthermore, those Offices do not require the applicant to furnish a copy of the international application (Rule 49.1(a-bis)).

3. Enclosed with this Notice is a copy of the international application as published by the International Bureau on 15 April 1999 (15.04.99) under No. WO 99/18474

REMINDER REGARDING CHAPTER II (Article 31(2)(a) and Rule 54.2)

If the applicant wishes to postpone entry into the national phase until 30 months (or later in some Offices) from the priority date, a demand for international preliminary examination must be filed with the competent International Preliminary Examining Authority before the expiration of 19 months from the priority date.

It is the applicant's sole responsibility to monitor the 19-month time limit.

Note that only an applicant who is a national or resident of a PCT Contracting State which is bound by Chapter II has the right to file a demand for international preliminary examination.

REMINDER REGARDING ENTRY INTO THE NATIONAL PHASE (Article 22 or 39(1))

If the applicant wishes to proceed with the international application in the national phase, he must, within 20 months or 30 months, or later in some Offices, perform the acts referred to therein before each designated or elected Office.

For further important information on the time limits and acts to be performed for entering the national phase, see the Annex to Form PCT/IB/301 (Notification of Receipt of Record Copy) and Volume II of the PCT Applicant's Guide.

The International Bureau of WIPO 34, chemin des Colombettes 1211 Geneva 20, Switzerland

Authorized officer

J. Zahra

Facsimile No. (41-22) 740.14.35

Telephone No. (41-22) 338.83.38

EL128 324327 US



INTERNATIONAL SEARCH REPORT

(PCT Article 18 and Rules 43 and 44)

Applicant's or agent's file reference	FOR FURTHER see Notification of	of Transmittal of International Search Report 220) as well as, where applicable, item 5 below.
30960116 WO	ACTION	
International application No.	International filing date (day/month/year)	(Earliest) Priority Date (day/month/year)
PCT/GB 98/03011	08/10/1998	08/10/1997
Applicant		
HEWLETT-PACKARD COMPANY e	t al.	
This International Search Report has bee according to Article 18. A copy is being tra	n prepared by this International Searching Autansmitted to the International Bureau.	thority and is transmitted to the applicant
This International Search Report consists X It is also accompanied by a cop	of a total of sheets. by of each priorart document cited in this repor	t
1. Certain claims were found un	searchable (see Box I).	
2. Unity of invention is lacking(see Box II).	
international search was carried	ontains disclosure of a nucleotide and/or amind out on the basis of the sequence listing	no acid sequence listing and the
	d with the international application. nished,by the applicant separately from the int	ernational application.
	but not accompanied by a statement to matter going beyond the disclosure in the	the effect that it did not include
Tra	anscribed by this Authority	
4. With regard to the title, X the	e text is approved as submitted by the applicar	nt
the	e text has been established by this Authority to	read as follows:
5. With regard to the abstract,		·
	e text is approved as submitted by the applica	
	e text has been established, according to Rule ox III. The applicant may, within one month fro earch Report, submit comments to this Authori	mthe date of mailing of this international
6. The figure of the drawings to be pu	blished with the abstract is:	
	s suggested by the applicant.	None of the figures.
be	ecause the applicant failed to suggest a figure.	-
be	ecause this figure better characterizes the inve	ention.

-3

INTERNATIONAL SEARCH REPORT



A. CLASSIFICATION OF SUBJECT MATTER IPC 6 G02F1/1337

According to International Patent Classification (IPC) or to both national classification and IPC

B. FIELDS SEARCHED

Minimum documentation searched (classification system followed by classification symbols)

IPC 6 GO2F

Documentation searched other than minimum documentation to the extent that such documents are included in the fields searched

Electronic data base consulted during the international search (name of data base and, where practical, search terms used)

Category °	Citation of document, with indication, where appropriate, of the relevant passages	Relevant to claim No.
X	GB 2 286 893 A (SECR DEFENCE) 30 August 1995 cited in the application	1,13,18, 19, 23-32, 44,54,57
	see page 1, paragraph 2 - paragraph 3 see page 3, paragraph 6 see page 4, paragraph 11 see page 6, paragraph 5 see page 9, paragraph 3 * Abstract *	
X	GB 2 286 466 A (SECR DEFENCE) 16 August 1995 cited in the application see page 1, paragraph 1 - paragraph 3 see page 6, paragraph 3 see page 7, paragraph 3 * Abstract *	1,13,18, 19,23-32

Further documents are listed in the continuation of box C.	Patent family members are listed in annex.
 Special categories of cited documents: "A" document defining the general state of the art which is not considered to be of particular relevance "E" earlier document but published on or after the international filing date "L" document which may throw doubts on priority claim(s) or which is cited to establish the publication date of another citation or other special reason (as specified) "O" document referring to an oral disclosure, use, exhibition or other means "P" document published prior to the international filing date but later than the priority date claimed 	"T" later document published after the international filing date or priority date and not in conflict with the application but cited to understand the principle or theory underlying the invention "X" document of particular relevance; the claimed invention cannot be considered novel or cannot be considered to involve an inventive step when the document is taken alone "Y" document of particular relevance; the claimed invention cannot be considered to involve an inventive step when the document is combined with one or more other such documents, such combination being obvious to a person skilled in the art. "&" document member of the same patent family
Date of the actual completion of the international search	Date of mailing of the international search report
18 December 1998	04/01/1999
Name and mailing address of the ISA	Authorized officer
European Patent Office, P.B. 5818 Patentiaan 2 NL - 2280 HV Rijswijk Tel. (+31-70) 340-2040, Tx. 31 651 epo ni, Fax: (+31-70) 340-3016	Petitpierre, O

1

INTERNATIONAL SEARCH REPORT

International Application No GB 98/03011

		703011
C.(Continu	ation) DOCUMENTS CONSIDERED TO BE RELEVANT	 Delegant to stain No.
Category °	Citation of document, with indication, where appropriate, of the relevant passages	Relevant to claim No.
X	US 5 040 876 A (PATEL JAYANTILAL S ET AL) 20 August 1991 see column 1, line 67 - column 2, line 2 see column 2, line 18 - line 26 see column 2, line 65 - column 3, line 18 see column 3, line 19 - line 38 see column 3, line 50 - line 56	1,18, 23-32
X	US 4 577 930 A (YANG KEI-HSIUNG) 25 March 1986 see column 1, line 25 - line 33 see column 3, line 1 - line 15 see column 3, line 65 - line 68 see column 6, line 4 - line 8 see column 6, line 56 - line 67	1,13,18, 19, 23-35, 39,40,43

1

INTERNATIONAL SEARCH REPORT

Informion on patent family members

International Application No

GB 98/03011

Patent documen cited in search rep		Publication date	ı	Patent family member(s)	Publication date
GB 2286893	Α	30-08-1995	CA	2182964 A	17-08-1995
	•••		CN	1145120 A	12-03-1997
			DE	69501395 D	12-02-1998
			DE	69501395 T	16-04-1998
			EP	0744039 A	27-11-1996
			ES	2111392 T	01-03-1998
			WO	9522075 A	17-08-1995
			GB	2301447 A	04-12-1996
			JP	9508714 T	02-09-1997
			ÜS	5724113 A	03-03-1998
GB 2286466	A	16-08-1995	CA	2182963 A	17-08-1995
	•••	10 00 1000	CN	1145119 A	12-03-1997
			DE	69500923 D	27-11-1997
			ĐE	69500923 T	05-03-1998
			EP	0744042 A	27-11-1996
			ES	2108569 T	16-12-1997
			WO	9522078 A	17-08-1995
			GB	2301448 A	04-12-1996
			JP	9508717 T	02-09-1997
			SG	47941 A	17-04-1998
			US	5764325 A	09-06-1998
US 5040876	A	20-08-1991	CA	2022127 A	08-09-1991
		•	WO	9114200 A	19-09-1991
US 4577930		25-03-1986	EP	0095012 A	30-11-1983
	- •		JP	1728142 C	19-01-1993
			JP	4015926 B	19-03-1992
			JP	58209717 A	06-12-1983

T-12030137103

The demand must be filed directly with the competent International Preliminary Examining Authority or, if two or more Authorities are competent, with the one chosen by the applicant.

If two or more Authorities are competent, and the line below:

IPEA/ P

PCT

CHAPTER II

DEMAND

under Article 31 of the Patent Cooperation Treaty:

The undersigned requests that the international application specified below be the subject of international preliminary examination according to the Patent Cooperation Treaty and hereby elects all eligible States (except where otherwise indicated).

For	International Preliminary	Examining Authority	use only
Identification of IPEA		Date of receipt of DE	EMAND
Box No. I IDENTIFICATION OF T	HE INTERNATIONAL	APPLICATION	Applicant's or agent's file reference 30960116 WO
International application No.	International filing dat	te (day/month/year)	(Earliest) Priority date (day/month/year)
PCT/GB98.03011	8 October 1998 (08	8/10/98)	8 October 1997 (08/10/97)
Title of invention		<u> </u>	
Liquid Crystal Device Alignment			
Box No. II APPLICANT(S)			
Name and address: (Family name followed by the address must include page 1	given name; for a legal entity, footal code and name of country	ull official designation. y.)	Telephone No.:
.Hewlett-Packard Company 3000 Hanover Street Palo Alto			Facsimile No.:
CA 94304 USA			Teleprinter No.:
State (that is, country) of nationality:		State (that is, country,) of residence:
Name and address: (Family name followed by	given name; for a legal entity, i	full official designation. Th	e address must include postal code and name of country.)
The Secretary of State for Defence Defence Evaluation and Research Ively Road Famborough Hampshire GU14 0LX GB	e h Agency		
State (that is, country) of nationality:		State (that is, country) of residence:
Name and address: (Family name followed by BRYAN-BROWN, Guy Peter DERA Malvern St. Andrews Road Malvern Worcs. WR14 3PS GB	given name; for a legal entity.	full official designation. Th	ne address must include postal code and name of country.)
State (that is, country) of nationality:		State (that is, country	y) of residence:
Further applicants are indicated o	n a continuation sheet.		

Sheet No. 2...

PCT/GB98.03011

continuation of Box No. II APPLICANT(S)	
	oxes is used, this sheet should not be included in the demand.
Jame and address: (Family name followed by given name;	for a legal entity, full official designation. The address must include postal code and name of country.)
State (that is, country) of nationality: GB	State (that is, country) of residence: GB
Name and address: (Family name followed by given name; JONES, John Clifford DERA Malvern St. Andrews Road Malvern Worcs. WR14 3PS GB	for a legal entity, full official designation. The address must include postal code and name of country.)
State (that is, country) of nationality: GB	State (that is, country) of residence: GB
Name and address: (Family name followed by given name; SAGE, Ian Charles DERA Malvern St. Andrews Road Malvern Worcs. WR14 3PS GB	; for a legal entity, full official designation. The address must include postal code and name of country.)
State (that is, country) of nationality: GB	State (that is, country) of residence: GB
	e; for a legal entity, full official designation. The address must include postal code and name of country
State (that is, country) of nationality:	State (that is, country) of residence: GB

Sheet No. 3. . .

nternational application No. PCT/GB98.03011

Box No. III AGENT OR COMMON REPRESENTATIVE; OR ADDRESS FOR COR	RESPONDENCE
Common representative	
The following person is the applicant(s) also for international prel	iminary examination.
is hereby appointed and any earlier appointment of (an) agent(s)/common represen	
is hereby appointed and any earlier appointment of (an) agent(s)/continon represent	pary Examining Authority, in addition to
is hereby appointed, specifically for the procedure before the International Preliming the agent(s)/common representative appointed earlier.	
Name and address: (Family name followed by given name; for a legal entity, full official designation. The address must include postal code and name of country.)	Telephone No.: .
LAWRENCE, Richard Anthony	(0)117-312-8295
Hewlett-Packard Limited	Facsimile No.:
Intellectual Property Section	(0)117-312-8941
Filton Road Stoke Gifford	Teleprinter No.:
Bristol BS34 8QZ	
Address for correspondence: Mark this check-box where no agent or common respondence space above is used instead to indicate a special address to which correspondence Box No. IV BASIS FOR INTERNATIONAL PRELIMINARY EXAMINATION	presentative is/has been appointed and the should be sent.
Statement concerning amendments:*	, •
1. The applicant wishes the international preliminary examination to start on the basis of	
the international application as originally filed	
the description as originally filed	
as amended under Article 34	
the claims as originally filed	
as amended under Article 19 (together with any accompanying	ig statement)
as amended under Article 34	
the drawings as originally filed	
as amended under Article 34	
2. The applicant wishes any amendment to the claims under Article 19 to be consider	lered as reversed.
The applicant wishes the start of the international preliminary examination to be from the priority date unless the International Preliminary Examining Authority under Article 19 or a notice from the applicant that he does not wish to make such box may be marked only where the time limit under Article 19 has not yet expired	h amendments (Rule 69.1(d)). (This checked.)
Where no check-box is marked, international preliminary examination will start or as originally filed or, where a copy of amendments to the claims under Article 19 and/or under Article 34 are received by the International Preliminary Examining Authority bef or the international preliminary examination report, as so amended.	amendments of the international application amendments of the international application ore it has begun to draw up a written opinion
Language for the purposes of international preliminary examination:	
which is the language in which the international application was filed.	
which is the language of a translation furnished for the purposes of internat	ionai search.
which is the language of publication of the international application.	tianal maliminant avamination
which is the language of the translation (to be) furnished for the purposes of inte	mauonai preimminary examination.
Box No. V ELECTION OF STATES	
The applicant hereby elects all eligible States (that is, all States which have been design	nated and which are bound by Chapter II o
the PCT)	
excluding the following States which the applicant wishes not to elect:	

Sheet No. 4...

remational application No.
PCT/GB98.03011

Box No. VI CHECK LIST						
The demand is accompanied by the following elements Box No. IV, for the purposes of international prelim	nts, in the language referninary examination:	red to in	For Internation Examining Aureceived	nal Preliminary thority use only not received		
1. translation of international application	:	sheets				
2. amendments under Article 34	:	sheets				
3. copy (or, where required, translation) of amendments under Article 19	:	sheets				
4. copy (or, where required, translation) of statement under Article 19	:	sheets				
5. letter	:	sheets				
6. other (specify)	:	sheets				
The demand is also accompanied by the item(s) mark	ed below:					
1. fee calculation sheet	4.		explaining lack of signa			
2. separate signed power of attorney	5.	nucleotide	and or amino acid seque eadable form	uence listing in		
copy of general power of attorney; reference number, if any:	6.	other (spec				
Box No. VII SIGNATURE OF APPLICANT, AC	GENT OR COMMON	N REPRESI	ENTATIVE			
Next to each signature, indicate the name of the person signing and the capacity in which the person signs (if such capacity is not obvious from reading the demand). Richard Anthony Lawrence						
For Internation	al Preliminary Examini	ng Authority	use only			
1. Date of actual receipt of DEMAND:						
2. Adjusted date of receipt of demand due to CORRECTIONS under Rule 60.1(b):						
The date of receipt of the demand is AFTER the expiration of 19 months from the priority date and item 4 or 5, below, does not apply. The applicant has been informed accordingly.						
4. The date of receipt of the demand is Name 180.5.						
5. Although the date of receipt of the den is EXCUSED pursuant to Rule 82.	nand is after the expirat	ion of 19 mo	onths from the priority	date, the delay in arrival		
	For International Bureau	use only		<u> </u>		
Demand received from IPEA on:						

EP1787542512



PCT

INTERNATIONAL PRELIMINARY EXAMINATION REPORT

(PCT Article 36 and Rule 70)

Applicant's o	r agei	nt's file reference	COR EURTHER ACTION		ation of Transmittal of International	/ 416)
30960116	wo		FOR FURTHER ACTION	Preliminary	Examination Report (Form PCT/IPEA/	
International	applic	cation No.	International filing date (day/mor	nth/year)	Priority date (day/month/year)	
PCT/GB9	8/03	011	08/10/1998		08/10/1997	
International G02F1/13		nt Classification (IPC) or na	ational classification and IPC			
Applicant						
HEWLET	T-PA	CKARD COMPANY	et al.			
1. This in and is	terna trans	ational preliminary examinated to the applicant	nination report has been preparaccording to Article 36.	red by this Int	ernational Preliminary Examining A	Authority
2. This R	EPO	RT consists of a total o	f 8 sheets, including this cove	r sheet.		
be (s	een a ee R	mended and are the ba	sis for this report and/or sheet 607 of the Administrative Instru	s containing r	on, claims and/or drawings which hectifications made before this Authhe PCT).	nave ority
3. This r	eport	contains indications re	ating to the following items:		•	
1	Ø	Basis of the report				
11		Priority				
111	\boxtimes	Non-establishment of	opinion with regard to novelty,	inventive step	and industrial applicability	
IV		Lack of unity of invent				
V	×	Reasoned statement citations and explanat	under Article 35(2) with regard tions suporting such statement	to novelty, in	entive step or industrial applicabili	ity;
VI		Certain documents c				
VII			international application			
VIII	⊠	Certain observations	on the international application	l		
Date of sub	missi	on of the demand	Date	of completion	of this report	
10/04/19	99				1 9. 01. 00	
	ехал	ng address of the internation ining authority:	nal Autt	norized officer	Ph. P.	COES MIZHER
9)	D-8	opean Patent Office 10298 Munich . +49 89 2399 - 0 Tx: 5236		itpierre, O	THE SEN WITH	<u> </u>
	Fax	c +49 89 2399 - 4465	Tele	phone No. +49	89 2399 2748	

INTERNATIONAL PRELIMINARY EXAMINATION REPORT

International application No. PCT/GB98/03011

1. B	asis	of	the	re	por	t
------	------	----	-----	----	-----	---

1. This report has been drawn on the basis of (substitute sheets which have been furnished to the receiving Office in response to an invitation under Article 14 are referred to in this report as "originally filed" and are not annexed to the report since they do not contain amendments.):

	the report since they do not contain amendments.):								
	Description, pages:								
	1-52		as originally filed						
	Clai	ms, No.:							
	1-59		as originally filed						
	Dra	wings, sheets:							
	1/10)-10/10	as originally filed						
•	The	amandments have	e resulted in the cancellation of:						
2.	i Ne	amendinents have	resulted in the carroomation of						
		the description,	pages:						
		the claims,	Nos.:						
		the drawings,	sheets:						
3.		This report has be considered to go	een established as if (some of) the amendments had not been made, since they have been beyond the disclosure as filed (Rule 70.2(c)):						
4.	Add	ditional observation	s, if necessary:						
			of opinion with regard to novelty, inventive step and industrial applicability						
TI OI	ne qu to b	uestions whether the industrially applic	ne claimed invention appears to be novel, to involve an inventive step (to be non-obvious), cable have not been examined in respect of:						
	☐ the entire international application.								
	Ø	claims Nos. 21,30	6,41,42.						
b	ecau	se:							

INTERNATIONAL PRELIMINARY **EXAMINATION REPORT**

International application No. PCT/GB98/03011

	the said international application, or the said claims Nos. relate to the following subject matter which does not require an international preliminary examination (specify):
×	the description, claims or drawings (indicate particular elements below) or said claims Nos. 21,36,41,42 are so unclear that no meaningful opinion could be formed (specify):
	see separate sheet
	the claims, or said claims Nos. are so inadequately supported by the description that no meaningful opinion could be formed.
	no international search report has been established for the said claims Nos

V. Reasoned statement under Article 35(2) with regard to novelty, inventive step or industrial applicability; citations and explanations supporting such statement

1. Statement

Claims 2-12,14-17,20,37,38,45-53,59 Yes: Novelty (N)

Claims 1,13,18,19,22-35,39,40,43,44,54-58 No:

Claims 2-12,14-17,20,37,45-53,59 Inventive step (IS)

Yes:

Claims 1,13,18,19,22-35,38-40,43,44,54-58 No:

Claims 1-59 Industrial applicability (IA) Yes:

Claims No:

2. Citations and explanations

see separate sheet

VIII. Certain observations on the international application

The following observations on the clarity of the claims, description, and drawings or on the question whether the claims are fully supported by the description, are made:

see separate sheet

Part V: novelty and inventive step (Art. 33 PCT)

- Independent claim 1 does not satisfy the requirements of Article 33(1) PCT because its subject matter is not novel within the meaning of Article 33(2) PCT.
 - All four documents of the International Search Report, namely, GB-A-2 286 893 (=D1), GB-A-2 286 466 (=D2), US-A-5 040 876 (=D3), and US-A-4 577 930 (=D4) disclose a liquid crystal device comprising a layer of a liquid crystal material contained between two spaced cell walls carrying electrode structures and an alignment treatment on at least one wall [D1: first sentence of Abstract and Fig. 1; D2: first paragraph of page 1 and Fig. 1; D3: column 3, lines 19-38; D4: column 6, lines 56-67], as well as means for reducing anchoring energy at the surface alignment on one of both cell walls [D1: third paragraph of page 9; D2: third paragraph of page 7; D3: column 1, line 67, to column 2, line 2; column 2, lines 18-26; and column 3, lines 50-56; D4: column 3, lines 12-15 and 65-68].
- Claims 2 to 12, appear to satisfy the requirements of Article 33(1) PCT because their subject matter is novel and furthermore involves an inventive step within the meaning of Article 33(3) PCT.
- 2.1 All four documents **D1** to **D4** disclose means for reducing anchoring energy which are part of the aligning surface. Therefore, it would not be a routine step on the part of a skilled person to replace such means by an oligomer or a short-chain polymer within the liquid crystal, as recited in claim 2.
- 2.2 Claim 3 relates to specific examples of the oligomer recited in claim 2, while claims 4 to 12 relate to specific embodiments of the device of claim 2.
- Independent claim 13 does not satisfy the requirements of Article 33(1) PCT because its subject matter is not novel.
 - This claim in fact relates to a method of manufacturing the device of claim 1 and is not novel for the same reasons as already explained in point 1 above.

INTERNATIONAL PRELIMINARY InterEXAMINATION REPORT - SEPARATE SHEET

- Despite their lack of clarity (see part VIII, point 1, below), it would appear that the subject matter of claims 14 to 17 is novel and involves an inventive step for the same reasons as already explained in point 2 above.
- Independent claim 18 does not satisfy the requirements of Article 33(1) PCT because its subject matter is not novel.
 - The only difference between claim 18 and claim 1 is the fact that the device is a TN device comprising "means for distinguishing between the two different optical states of the liquid crystal material", namely, polarizers. These features are however known from **D1** [page 1, lines 1-7 of third paragraph, and fifth paragraph of page 6], **D2** [page 1, lines 1-7 of third paragraph, and third paragraph of page 6], **D3** [column 2, line 65, to column 3, line 18], and **D4** [column 1, lines 25-33].
- Claims 19 and 22 to 32 do not satisfy the requirements of Article 33(1) PCT because their object is not novel. Moreover, no statement concerning claim 21 can be given in view of the lack of clarity of the latter (see part VIII, point 2 below).
 - It would appear that the subject matter of claim 20 is novel and involves an inventive step for the reasons already recited in point 2 above.
- 6.1 The device of claim 19 is disclosed in D1 [third paragraph of page 9]; D2 [last sentence of Abstract]; and D4 [column 3, lines 12-15]
- 6.3 Concerning claim 22, **D1** discloses that a layer of polyvinylcinnamate, which is an ester, is deposited as alignment layer on the substrates [page 7, lines 1-3].
- 6.4 Claims 23 to 32, which all depend on claim 18, only recite standard features of TN-LCDs which are either implicitly or explicitly disclosed in **D1** to **D4**.
- Independent claim 33 does not satisfy the requirements of Article 33(1) PCT because its subject matter is not novel within the meaning of Article 33(2) PCT.
 - The device of this claim is disclosed in **D4** [column 3, lines 1-2 and 12-15; column 3, line 61, to column 4, line 16; and column 6, lines 4-8; the inelastic azimuthal

INTERNATIONAL PRELIMINARY

EXAMINATION REPORT - SEPARATE SHEET

memory anchoring force is inherently lowered when the overall anchoring force is lowered].

Claims 34, 35, 38, 39, 40, and 43 do not satisfy the requirements of Article 33(1) PCT because the subject matter of claims 34, 35, 39, 40, and 43 is not novel and the subject matter of claim 38 does not involve an inventive step.

It would appear that the subject matter of claim 37 is novel and involves an inventive step for the reasons already recited in point 2 above.

A statement concerning the novelty of or the presence of an inventive step in the subject matter of claims 36, 41, and 42 cannot be given in view of the lack of clarity of these claims (see part VIII, point 2 below).

- 8.1 The device of claims 34, 35, 39, 40, and 43 is implicitly disclosed in **D4** [column 3, lines 1-2 and 12-15; column 3, line 61, to column 4, line 16; and column 6, lines 4-8; moreover, both the azimuthal and the zenithal anchoring forces are inherently lowered when the overall anchoring force is lowered].
- 8.2 Although **D4** does not disclose the chain length recited in claim 38, such a parameter is a routine design parameter which does not require any inventive step on the part of the skilled person.
- Independent claim 44 does not satisfy the requirements of Article 33(1) PCT because its subject matter is not novel.

The only difference between this claim and claim 1 is that the liquid crystal is smectic. This feature is however known from **D1** [second paragraph of page 1; last paragraph of page 4; and last paragraph of page 10].

Claims 45 to 50, 53, 59, and, as far as they could be understood (see part VIII, point 4 below), claims 51 and 52 appear to satisfy the requirements of Article 33(1) PCT because their subject matter is novel and involves an inventive step.

Claims 54 to 58, however, do not satisfy the requirements of Article 33(1) PCT because their subject matter is not novel.

- 10.1 Claim 45 recites per se the same features as recited in claim 2, so that its subject matter is novel and inventive for the reasons already explained in point 2.1 above.
- 10.2 Claims 46 to 50 and, as far as they could be understood, claims 51 and 52 relate to specific embodiments of the device of claim 45.
- 10.3 None of the prior art documents **D1** to **D4** disclose a device wherein: (i) the liquid crystal material is a **chiral** smectic material; (ii) and the alignment directions on the two cell walls are substantially **parallel**, as recited in claim 53.
- 10.4 The device of claims 54 to 58 is known from D1 [page 6, fifth paragraph; page 4, last paragraph; page 3, sixth paragraph; and page 1, last paragraph].
- 10.5 Although **D3** discloses that the substrates may exhibit different aligning properties, this document, as well as documents **D1**, **D2**, and **D4** do not disclose or even suggest a device wherein one cell wall has an alignment treatment and the other one has no azimuthal alignment direction and wherein both cell walls are treated with the means for reducing anchoring energy, as recited in claim 59.

Part VIII: clarity (Art. 6 PCT)

- Claims 14 to 17 should probably depend on claim 13 and not 11. Moreover, claims 14 to 17 refer to an "oligomer or short chain polymer" although no such oligomer or short chain polymer has been previously defined.
- Claim 21 refers to two chemical compounds by their respective trade name. Such names however introduce a lack of clarity in the scope of these claims since the exact composition of these chemical compounds is not disclosed or may vary in time.

INTERNATIONAL PRELIMINARY International application No EXAMINATION REPORT - SEPARATE SHEET

International application No. PCT/GB98/03011

Since the chemical composition of N65 and MXM035 has not been recited in the documents as originally filed, it would appear impossible to amend this claim while satisfying the requirements of Article 34(2)(b) PCT.

The same objection applies in part to claim 36.

3. The scope of claims 41 and 42 is unclear.

The only feature recited per se in these claims is a method step the presence of which can no longer be determined from the manufactured device.

4. Claims 51 and 52 should probably depend on claim 45 and not 44 since the oligomer or short chain polymer is first defined in claim 45.

PCT

WORLD INTELLECTUAL PROPERTY ORGANIZATION International Bureau



INTERNATIONAL APPLICATION PUBLISHED UNDER THE PATENT COOPERATION TREATY (PCT)

(51) International Patent Classification 6	:
COOF 1/1/327	

(11) International Publication Number:

WO 99/18474

G02F 1/1337

(43) International Publication Date:

15 April 1999 (15,04.99)

(21) International Application Number:

PCT/GB98/03011

A1

(22) International Filing Date:

8 October 1998 (08.10.98)

(30) Priority Data:

9721214.6 8 October 1997 (08.10.97) GB 9721215.3 8 October 1997 (08.10.97) GB 9721229.4 8 October 1997 (08.10.97) GB 9721256.7 8 October 1997 (08.10.97) GB

(71) Applicants (for all designated States except US): HEWLETT-PACKARD COMPANY [US/US]; 3000 Hanover Street, Palo Alto, CA 94304 (US). THE SECRETARY OF STATE FOR DEFENCE [GB/GB]; Defence Evaluation and Research Agency, Ively Road, Pamborough, Hampshire GU14 OLX (GB).

(72) Inventors; and

(75) Inventors/Applicants (for US only): BRYAN-BROWN, Guy, Peter [GB/GB]; DERA Malvern, St. Andrews Road, Malvern, Worcs. WR14 3PS (GB). HUI, Victor, Chaklam [GB/GB]; DERA Malvern, St. Andrews Road, Malvern, Worcs. WR14 3PS (GB). JONES, John, Clifford [GB/GB]; DERA Malvern, St. Andrews Road, Malvern, Worcs. WR14 3PS (GB). SAGE, Ian, Charles [GB/GB]; DERA Malvern, St. Andrews Road, Malvern, Worcs. WR14 3PS

(GB). WOOD, Emma, Louise [GB/GB]; DERA Malvern, St. Andrews Road, Malvern, Worcs. WR14 3PS (GB).

(74) Agent: LAWRENCE, Richard, Anthony; Hewlett-Packard Limited, Intellectual Property Section, Filton Road, Stoke Gifford, Bristol BS34 8QZ (GB).

(81) Designated States: CN, JP, KR, SG, US, European patent (AT, BE, CH, CY, DE, DK, ES, FI, FR, GB, GR, IE, IT, LU, MC, NL, PT, SE).


Published

With international search report.

(54) Title: LIQUID CRYSTAL DEVICE ALIGNMENT

(57) Abstract

Liquid crystal devices are formed by a layer of a liquid crystal material enclosed between two cell walls, both carrying electrode structures, and one or both walls treated to align molecules of the liquid crystal material. Most alignment treatment give alignment and surface pretilt with a strong azimumal and zenithal anchoring energy to contacting liquid crystal molecules. The invention reduces at least one of the azimuthal zenithal or translational anchoring energy to improve switching characteristics and optical performance by allowing movement of liquid crystal molecules at or close to the cell wall. The reduction of anchoring energy may be achieved by an oligomer or short chain polymer which is either spread on the surface or added to the liquid crystal material. The size of oligomer or short chain polymer is low enough that it does not appreciably phase separate from the liquid crystal material. The polymer layer has the characteristics of having imperfect solubility in the liquid crystal material used in the device, of having a physical affinity for the surface of the



substrate, and of retaining a substantially liquid like surface at the polymer/liquid crystal interface. The polymer may be formed by polymerisation of reactive low molecular weight materials in solution in the liquid crystal fluid. The resulting solution or dispersion of polymer in liquid crystal is then filled into the cell, and the polymer is allowed to coat the substrate surfaces.

FOR THE PURPOSES OF INFORMATION ONLY

Codes used to identify States party to the PCT on the front pages of pamphlets publishing international applications under the PCT.

l	AL	Albenta	ES	Spain	LS	Lesotho		
	MA	Алпенія	FI	Finland	LT	Lithuania	SI	Slovenia
	AT	Austria	FR	Prance	້າກ		SK	Slovakia
ı	ΑU	Australia	GA	Gabon		Luxenbourg	SN	Senegal
	AZ	Azerbaijan	GB		LV	Latvia	SZ	Swaziland
	BA	Bosnia and Herzegovina	CE	United Kingdom	MC	Monaco	TD	Chad
	BB	Barbados		Ocorgia	MD	Republic of Moldova	TG	Togo
	BE		GH	Citana	MG	Madagascar	TJ	Tajikistan
		Belgium	GN	Guinea	MIK	The former Yugoslav	TM	Torkmenistan
	B¥	Burkina Faso	GR	Greece		Republic of Macedonia	TR	Turkey
	BG	Bulgaria	HU	Hungary	ML	Mali	TT	•
	BI	Benin	IB	Ireland	MN	Mongolia		Trinidad and Tobago
	BR	Brazil	TL.	Israel	MR	Mauritania	UA	Ukraine
	BY	Behrus	IS	Teeland	MW	· =	UG	Uganda
	CA	Canada	IT	Italy		Malawi	US	United States of America
	CP	Central African Republic	JP	•	MX	Mexico	UZ	Uzbekistan
	CG	Congo	_	Japan	NE	Niger	VN	Vict Nam
	CH	Switzerland	KE	Хенув	NL	Netherlands	YU	Yugoslavia
	a.	_	KG	Kyrgyzstan	NO	Norway	ZW	Zimbabwe
	CM	Côte d'Tvoire	KP	Democratic People's	NZ	New Zealand		<u></u>
		Curreroon		Republic of Korea	PL.	Poland		
	CN	China	KR	Republic of Korea	PT	Portugal		
	CU	Cuba	KZ	Kazakstan	RO	Romania		
	CZ	Czech Republic	LC	Saint Lucia	RU			
	DE	Germany	u	Liechtenstein		Russian Federation		
	DK	Denmark	LK	Sri Lanta	SD	Sodan		
	EE	Estonia	LR		SE	Sweden		
		-	~~	Liberia	SG	Singapore		

LIQUID CRYSTAL DEVICE ALIGNMENT

This invention relates to liquid crystal device alignment.

- Liquid crystal devices typically comprise a thin layer of a liquid crystal material contained between cell walls or substrates. Optically transparent electrode structures on the walls allow an electric field to be applied across the layer, causing a reordering of the liquid crystal molecules.
- Many different modes of liquid crystal devices are known in the art, for example the twisted nematic device, the cholesteric phase change device, the dynamic scattering device, the supertwisted nematic device and the surface stabilised ferroelectric device modes. It is well known in all of these device modes to provide a surface on the interior walls of the device which will control the alignment of the liquid crystal fluid in close proximity to the surface. For many applications of liquid crystal devices, such a treatment is considered necessary in order to impose a particular configuration on the alignment of the liquid crystal fluid throughout the device and/or to provide an optical appearance in the device which is free of apparent optical defects. The particular significance of this factor for different classes of liquid crystal device is described in greater detail below.

The terms azimuth or azimuthal is used herein to define the molecular (or director n) alignment angle movement or energy in the plane of the substrate surface. The terms zenith or zenithal is used herein to define the molecular alignment angle movement or energy in a plane normal to the substrate surface.

25

30

In respect of use of nematic and long pitch cholesteric materials for devices known as twisted nematic liquid crystal devices, the relevance of alignment and the problems associated therewith are as follows.

In order to provide displays with a large number of addressable elements it is common to make the electrodes as a series of row electrodes on one wall and a series of column electrodes on the other cell wall. These form typically an x,y matrix of addressable

elements or pixels and for twisted nematic types of device are commonly addressed using rms addressing methods.

Twisted nematic (TN) and phase change devices are switched to an ON state by application of a suitable voltage and allowed to switch to an OFF state when the applied voltage falls below a lower voltage level, i.e. these devices are monostable. For a twisted nematic type of device (90° or 270° twist as in US 4,596,446) the number of elements that can be rms addressed is limited by the steepness of a device transmission verses voltage curve (as described by Alt and Pleschko in IEEE Trans ED vol ED 21, (1974) P.146 - 155). One way of improving the number of pixels is to incorporate thin film transistors adjacent to each pixel; such displays are termed active matrix displays.

An advantage of nematic types of devices is the relatively low voltage requirements. They are also mechanically stable and have a wide temperature operating range. This allows construction of small and portable battery powered displays. An alternative twisted nematic device is one which is switched from a non-twisted state at zero volts to a twisted state at a higher voltage, as described in GB 9607854.8, which will be referred to in this patent as a VCT device.

20

25

30

10

One problem with the twisted nematic device is that the contrast ratio of a normally white display remains at a low value until the voltage is increased to a value considerably higher than the threshold voltage. This is due to the nematic material close to the cell walls which does not fully reorient in the applied field due to the strong zenithal anchoring imposed by the surface alignment layer. This lack of surface reorientation also leads to higher voltage operation in the VCT device.

In respect of use of nematic and long pitch cholesteric materials for devices known as bistable nematic liquid crystal devices, the relevance of alignment and the problems associated therewith are as follows.

As described above, twisted nematic and phase change type of liquid crystal devices are switched to an ON state by application of a suitable voltage, and allowed to switch

to an OFF state when the applied voltage falls below a lower voltage level, i.e. these devices are monostable. An advantage of nematic type of devices is that they have relatively low voltage requirements. They are also mechanically stable and have wide temperature operating ranges. This allows construction of small and portable battery powered displays. A disadvantage of such devices is that their monostable switching characteristic limits the number of lines that can be multiplex addressed.

Another way of addressing large displays is to use a bistable liquid crystal device. Ferroelectric liquid crystal displays can be made into bistable devices with the use of smectic liquid crystal materials and suitable cell wall surface alignment treatment. Such a device is a surface stabilised ferroelectric liquid crystal device (SSFELCDs) as described by:- L J Yu, H Lee, C S Bak and M M Labes, Phys Rev Lett 36, 7, 388 (1976); R B Meyer, Mol Cryst Liq Cryst. 40, 33 (1977); N A Clark and S T Lagerwall, Appl Phys Lett, 36, 11, 899 (1980). One disadvantage of ferroelectric devices is the relatively large voltage needed to switch the material. This high voltage makes small portable, battery powered displays expensive. Also these displays suffer from other problems such as lack of shock resistance, limited temperature range and also electrically induced defects such as needles.

10

15

30

If a bistable switching characteristic can be achieved using nematics then a display can be made which has the merits of both the above mentioned technologies but without their problems.

It has already been shown by Durand et al that a nematic can be switched between two alignment states via the use of chiral ions or flexoelectric coupling: A Charbi, R 25 Barberi, G Durand and P Martinot-Largarde, Patent Application No WO 91/11747, (1991) "Bistable electrochirally controlled liquid crystal optical device", G Durand, R Barberi, M Giocondo, P Martinot-Largarde, Patent Application No WO 92/00546 (1991) "Nematic liquid crystal display with surface bistability controlled by a flexoelectric effect".

Patent US 4,333,708 describes a multistable liquid crystal device in which cell walls are profiled to provide an array of singular points. Such substrate configurations

4

provide multistable configurations of the director alignments because disclination must be moved to switch between stable configurations. Switching is achieved by application of electric fields.

Patent Application No:. WO97/14990, (PCT-96/02463, GB95 21106.6) describes a bistable nematic device having a grating surface treatment to at least one cell wall that permits nematic liquid crystal molecules to adopt either of two pretilt angles in the same azimuthal plane. The cell can be electrically switched between these two states to allow information display which can persist after the removal of power.

10

15

Another bistable nematic device is described in GB.2,286,467-A. This uses accurately formed bigratings on at least one cell wall. The bigrating permits liquid crystal molecules to adopt two different angular aligned directions when suitable electrical signals are applied to cell electrodes, e.g. dc coupling to flexoelectric polarisation as described in Patent Application No. WO.92/00546. Since in the two splayed states the director is quite close to being in the plane of the layer, the coupling between director and flexoelectric component can be small, which may hinder switching in some circumstances.

The bistable nematic device of GB2286467-A also has a further problem which is not present in ferroelectric devices, that is, the need to switch the surface layer of molecules in order to eliminate image sticking effects. Surface layer switching usually requires high voltages which leads to both high power consumption and the need for customised driver circuitry.

25

In respect of devices using smectic materials, the relevance of alignment and the problems associated therewith are as follows.

There are a number of devices based on smectic liquid crystal materials including:

30

A: Ferroelectric liquid crystals (usually SmC*).

One example of this is bistable, and is often termed a surface stabilised FLC device (SSFLC) ref. N. A. Clark and S. T. Lagerwall, Appl. Phys. Lett., 36, 899 (1980). In this device planar aligned surfaces are arranged with parallel or anti parallel preferred alignment directions. The device is cooled from an overlying Smectic A phase into a bookshelf arrangement of the smectic layers, that is the material forms into micro layers arranged normal to the cell walls as in books on a shelf.

In the original teaching, the device used an unrubbed polymer surface alignment treatment to ensure the liquid crystal director n lies preferentially and substantially parallel to the surface plane (i.e. \bot to s, the surface normal). A preferred direction was then imparted by heating to the smectic A phase and shearing the layers in the required direction. The layers remained fixed on cooling into the SmC* phase. The surface energy is minimum for $n \bot s$ so that two minimum energy states occur which can be selected by suitable DC electric field.

15

20

10

Bradshaw and Raynes realised that improved SmA alignment for such a device resulted by having a chiral nematic N* phase above the SmA in which the pitch was sufficiently long for the surface forces to cause unwinding of the spontaneous helicity for a significant temperature range above the transition. They also required that the surface should be pre-treated to impart the preferred directions, often by use of parallel or antiparallel rubbing of a polyimide or polyamide layer; GB-2,210,469 USP-4,997,264, GB-2,209,610, USP-5,061,047, GB-2,210,468.

Later it was found that when a bookshelf aligned (where the layer normal is parallel to the plane of the device i.e. δ =0) SmA sample is cooled into the SmC* phase, the layers become tilted in a chevron type of configuration; two type of chevron can exist and are defined as C_1 and C_2 type (ref J.Kanbe et al Ferroelectrics (1991) vol 114, pp3). These are shown in Figure 18. This has been ascribed to the combined effect of shrinkage of the smectic layer spacing and pinning of the layers at the surface. The resulting chevron structure means that the director in the middle of the cell is (roughly) fixed in one of two orientations significantly less than the full cone angle. This means that with no applied field there is a substantial drop in the angle between the optic axis of the two "surface stabilised" states which leads to a corresponding

drop of the display brightness. A number of methods of improving the optical brightness have been proposed for practical devices:

1 AC field stabilisation:

An applied AC field pulse of insufficient time and voltage (τ V) to latch into the two states couples to the dielectric tensor (primarily the dielectric biaxiality) to increase the angle between these states and enhance the brightness. The main problem with this type of approach is that a high frequency voltage is required constantly to maintain the required brightness. This causes a high power dissipation, particularly for complex displays where the applied frequency is high. Usually the brightness is compromised by using a suitably low AC voltage. It has the advantage that, if C2U type alignment is used, there is no need for surface switching, and hence surface memory effects are minimal, and the slower switching at the surface does not effect the device.

15

20

30

10

2 High pre-tilt Parallel:

This geometry has (approximately) the same chevron structure with the director at the chevron interface also at a low angle to the rubbing direction. However, the director at the surface is at a much higher in-plane twist angle due to the competing effects of lying on the SmC* cone and with the preferred alignment pre-tilt. This type of device gives good brightness but suffers from a slower response since it involves surface switching, and from strong surface memory problems which may lead to image sticking.

25 3 Quasi-bookshelf:

Two methods may be used to reduce the layer tilt angle and thereby increase the device brightness. Pre-treating the device with a low frequency field of sufficient magnitude or choosing certain materials in which the layer shrinkage on cooling through the smectic phases is reduced (some materials may actually increase layer spacing on cooling). Such a device has similar advantages and disadvantages to the high pre-tilt configurations.

4 Uniform Tilted layer (High pre-tilt anti-parallel) geometry:

Similar to previous two geometry's but there is no chevron (and therefore no constraint on the director at the cell centre) and the high angle between the bistable states is stabilised solely by the surfaces.

5

10

B: Electro-clinic optical shutters:

Application of a DC field to the smectic A (or other orthogonal smectic) phase of a chiral material leads to an induced tilt of the director and hence optical axis normal to the applied field. In a (approximately) planar aligned liquid crystal cell with electrodes on the substrate surfaces the electroclinic effect induces a rotation of the optic axis by an angle proportional to the applied field E. Thus, an optical shutter with full analogue amplitude or phase modulation may be obtained.

A common problem with such a device is obtaining suitably uniform and planar alignment of the smectic layers. A lesser problem is that the induced switching may involve some rotation of the director away from the preferred alignment direction at the surface. This movement is subject to a surface viscosity which may impede the switching time of the device and also to certain surface memory effects.

20

25

C: Anti-ferroelectric smectic liquid crystals (AFLC):

Certain materials form an anti-ferroelectric phase which may be used in active matrix or direct drive devices. Effectively these devices have a similar appearance to the smectic A phase until sufficient DC voltage is applied, above which the sample is in either of two states (depending on the polarity of the applied signal) similar to the normal ferroelectric phase.

There is a limited number of materials which form this phase (particularly over a wide temperature range) and all those found so far have direct isotropic to smectic phase (i.e. no overlying chiral nematic phase). This means that the materials are more difficult to align, forming batonnets (see Gray and Goodby book) of the smectic at this transition.

The mechanism for this is that the smectic layer structure nucleates in a limited number of "cold spots" in the isotropic liquid. The layers then curve around this point to minimise the bend and splay of the layer normal. Where the layers meet the surface they become pinned and difficult to move. Hence, it is difficult to obtain the desired layer arrangement (e.g. planar or bookshelf) once the batonnet structure has pre-formed. On cooling into the AFLC phase, the applied field tends to induce twist of the director at the surfaces which also leads to problems associated with surface switching such as slower speed, surface memory effects, etc.

D: SmC* Optical Shutters:

10

Bradshaw and Raynes also described a type of device in which the FLC is obtained from cooling directly from the unwound N* phase in a parallel rubbed device, preferably with in applied DC field applied during the phase transition. The unwound N* phase has the director in the rubbing directions and on cooling into the SmC* this orientation is maintained and the layer normal twists through the angle θ. Degeneracy of the direction in which the layer normal is oriented is removed by the application of the DC field.

This is a monostable device, since it always relaxes back to the surface stabilised state (with n | s) once the field is removed (it may be used in devices when the field is retained, either through AC stabilisation or through inclusion of TFTs or similar non-linear electrical elements at each pixel. However, it is fast (due to Ps). Primarily switching occurs in the bulk of the cell and little or no switching occurs at the surface. However, this means that the director is highly twisted and non uniform structure. This means that the optical appearance is poor (particularly if used in conjunction with a dye as done in early Hitachi work) and so this is a case where surface switching is required to improve performance. Also, alignment is difficult over a wide temperature range because layer shrinkage still occurs in many N-SMC* materials, leading to a chevron structure and associated defects.

Alignment of liquid crystals on a surface is therefore a significant problem for all these device types. Several different means are known by which liquid crystal fluids may be aligned on a surface. Evaporation of silicon monoxide from a direction at least 30° from the plane of the substrate provides a surface which aligns a nematic liquid crystal in the plane of the substrate, along an axis orthogonal to the evaporation direction. In contrast, if the evaporation is conducted from a direction making an angle of about 5° or less from the substrate, the resulting surface aligns a nematic liquid crystal along a direction tilted from the plane of the substrate by about 20° in the direction of the evaporation source.

Many commercial liquid crystal devices are fabricated using rubbed polymer alignment layers, especially rubbed polyimide alignment layers. Typically such layers are deposited as an amide precursor polymer by spin deposition of a solution. After removal of the solvent, the polymer coating is imidised by baking at high temperature, then unidirectionally rubbed with a cloth. The resulting surface aligns liquid crystal materials along the direction of rubbing with a tilt out of the plane of the surface in the direction of rubbing. The magnitude of the tilt angle is typically 1° to 2°, but special polyimide formulations and treatments are available which can provide higher magnitudes of pretilt. Some polymer layer are capable of aligning liquid crystal material when cross linked by exposure to linear polarised light (WO95/22075, GB-9444402516). This avoids the need for rubbing which is useful when substrates carry thin film transistors for a part of active matrix displays. The aligned polymer may also be used in conduction with gratings as noted below.

25

20

10

15

A further means to provide a surface alignment for liquid crystal materials is available from the deposition of different surfactant materials onto the substrate from solution. A range of different surfactants may be used, including quaternary ammonium salts, alkylated silazenes and basic chromium alkanoates. Treatment of the surface usually entails dipping or spin coating with a dilute solution of the surfactant, and usually results in an alignment of the liquid crystal orthogonal to the plane of the substrate, termed homeotropic alignment. Binuclear chromium alkanoates and other binuclear

10

surfactants may provide alignment in the plane of the substrate without any preferred direction in this plane.

Yet a further method to achieve liquid crystal alignment at a surface involves fabrication of a relief structure such as a relief grating on the surface. Such a structure may be obtained by photolithographic means, by embossing a compliant surface layer such as a polymer against a master structure fabricated on, for example, a metal sheet, by mechanically scribing the surface or by other means. A grating structure aligns a nematic liquid crystal along the direction of the troughs and crests of the grating. More complex relief structures can provide tilted or bistable alignment.

The alignment methods of the known art suffer a number of shortcomings which prevent liquid crystal devices manufactured according to these methods from achieving their full potential utility.

15

5

One such shortcoming is that it is hardly possible according to known methods, to provide a surface alignment treatment on which the liquid crystal alignment is free to adopt any alignment direction in the plane of the surface. A planar alignment may be obtained by various methods including evaporation of an inorganic material from substantially normal incidence to the substrate, or by coating the substrate with a known polymer material such as a polyimide material without mechanical rubbing. In these cases, the alignment of the liquid crystal on the surface is not fixed during the surface preparation, but is fixed by the alignment of the liquid crystalline phase which first contacts it, and then becomes immovable.

25

30

On such a surface the alignment direction is determined by such factors as the flow direction or the direction of a temperature gradient or electric fields at the time the liquid crystal phase first contacts the surface. It is desirable to provide a surface treatment which can allow the liquid crystal alignment direction to rotate freely and repeatedly in the surface plane, but this is not available from known surface treatments.

11

A second shortcoming of known liquid crystal alignment techniques is that the energy required to change the zenithal angle between the substrate and the liquid crystal director is much greater than the elastic distortion energy of the liquid crystal itself which is generated by commonly applied voltages. This means that in liquid crystal devices using known alignment techniques, the liquid crystal director remains substantially fixed in tilt angle at the cell walls and the switching of the device which provides an optical effect occurs only in the parts of the device which are separated from the cell walls by some distance which depends on the magnitude of the applied field.

10

15

20

25

30

The present inventors have found that the above problems are reduced by a surface alignment treatment which allows movement of liquid crystal molecules at or close to the cell walls, hence the liquid crystal director in contact with the wall to reversibly change its orientation at low values of applied field, for example at applied field strengths of the order of less than 1 volt per micron for an applied electric field. The benefits of such a surface treatment may include reduction in the operating voltage of the device and/or an improvement in the switching behaviour of the device such as the electro-optic threshold steepness of the device which determines the amount of information which may be written on an electro-optic display by means of the known methods of RMS multiplex driving.

Accordingly, in a first aspect the invention provides a liquid crystal device comprising a layer of a liquid crystal material contained between two spaced cell wall carrying electrodes structures and an alignment treatment on at least one wall, characterised by means for reducing anchoring energy at the surface alignment on one or both cell walls.

The anchoring energy reduced is one or more of: azimuthal anchoring energy, zenithal anchoring energy, and translational anchoring energy (movement along the alignment treated surface). The significance of anchoring energies in the context of different device types are discussed further below. Further aspects of the invention relevant to specific device types are also discussed further below.

12

Anchoring energy arises from surface topography features such as grooves or gratings, and from chemical bonding interactions. The present invention reduces anchoring energy by changing the chemical bonding. Additionally the surface topography may also be changed, for example to reduce the dimensions of grooves or gratings. The means for reducing energy may be an oligomer or short chain polymer which is either spread on the surface or added to the liquid crystal material. The size of oligomer or short chain polymer may be selected to give a desired amount of preferential deposition at cell walls and slight separation from the liquid crystal material host.

10

15

25

5

The means for reducing anchoring energy may be an oligomer containing esters, thiols, and/or acrylate monomers and or which is either spread on the surface or added to the liquid crystal material.

The alignment treatment and means for reducing anchoring energy may be provided by a double layer treatment, now referred to as a substrate layer and a polymer layer. The substrate layer may either be formed in the surface of the cell wall, e.g. by mechanical rubbing of the surface, or (and preferably) be a coating on the cell wall. This coating may include anisotropic features which act to align liquid crystal phases placed in contact with it or in close proximity to it. Such features may include surface relief features including a plain or blazed grating or bigrating structure, or a regular or irregular array of surface features including but not limited to columns, tilted columns, platelets and crystallites e.g. formed by normal or oblique evaporation of inorganic materials onto the surface or by mechanical abrasion or working of the surface. Such features may also include a substantial anisotropy in the substrate formed, for example, by mechanical stretching or rubbing of the substrate layer or by exposure of the substrate layer to polarised actinic radiation.

The polymer layer (formed on the substrate layer) has the characteristics of having imperfect solubility in the liquid crystal material used in the device, of having a **30** physical affinity for the surface of the substrate, and of retaining a substantially liquid like surface at the polymer/liquid crystal interface.

13

The polymer may be applied to the device in various ways. In one approach, the polymer is formed by polymerisation of reactive low molecular weight materials in solution in the liquid crystal fluid. The resulting solution or dispersion of polymer in liquid crystal is then filled into the cell, and the polymer is allowed to coat the substrate surfaces. Optionally, the dispersion of polymer in liquid crystal may undergo intermediate processes such as filtration or centrifuging prior to being filled into the display cell.

In a further approach to applying the polymer to the device the reactive low molecular mass materials may be dissolved into the liquid crystal which is then filled into the display cell. Polymerisation is then initiated by known means, such as by heating or exposure to short wavelength optical radiation in the presence of an initiator. After polymerisation the polymer is allowed to diffuse to and coat the substrate layers.

10

30

- A still further approach to applying the polymer to the device is provided by polymerisation of the reactive materials in the presence or absence of an inert solvent. The solvent, if present, is removed and the resulting polymer is dissolved in the liquid crystal and filled in to the display cell.
- A further approach to applying the polymer to the device is to form the polymer on the substrate by applying a thin layer of reactive low molecular weight materials to the substrate by known means such as by spinning a stoichiometric amount of each onto the substrate in solution in a solvent. After removal of the solvent, polymerisation is initiated by heating or by exposure to light in the presence of a polymerisation initiator. The treated substrates are then assembled into a cell and the liquid crystal added in.

The polymer is characterised in that it is substantially non-crystalline in the presence of the liquid crystal, and that it possesses a glass transition temperature below the operating temperature range of the device. The polymer may be substantially linear in its molecular structure or it may include branch points. The polymer may also be crosslinked to a low degree in order to promote phase separation from the liquid crystal and deposition onto the substrate, but such crosslinking is at such a level that a

14

fluid, gum-like, gel-like or elastic character is retained, and the polymer does not present a hard glassy or solid like character which is retained on heating.

Preferred polymeric materials include thiol/ene polymers prepared by free radical polymerisation of known monomers in the presence of an added thiol compound which serves to limit the molecular weight of the product through chain transfer reactions. Details of suitable material are listed later.

In relation to twisted nematic devices, the present inventors have found that the contrast ratio of a twisted nematic device can be improved by using an additional surface treatment which reduces the zenithal anchoring energy of the surface and thereby allows field-induced reorientation of the near-surface nematic layers. Such a treatment also has the added advantage of leading to a lowering of the threshold voltage. Lower voltage operation is preferable for both passive matrix and active matrix twisted nematic devices as it allows a display to operate with a lower power consumption.

10

15

20

25

30

Accordingly, in a second aspect the invention provides a twisted nematic liquid crystal device capable of being switched from a twisted stated to a non twisted state comprising; two cell walls enclosing a layer of nematic liquid crystal material; electrode structures on both walls for applying an electric field across the liquid crystal layer; a surface alignment on both cell walls providing alignment direction to liquid crystal molecules and arranged so that a twisted nematic structure is formed across the liquid crystal layer at either zero volts or at a higher voltage; means for distinguishing between the two different optical states of the liquid crystal material; CHARACTERISED BY means for reducing zenithal anchoring energy in the surface alignment on one or both cell walls.

Additionally the azimuthal anchoring energy may also be reduced.

The means for reducing azimuthal anchoring energy and zenithal anchoring energy may be an oligomer containing esters, thiol, and/or acrylate monomers either spread

5

15

20

on the surface or added to the liquid crystal material, e.g. the materials N65 and MXM035.

The oligomers may migrate preferentially to the surface in order to minimise the surface free energy. This may dilute the amount of liquid crystal at the surface leading to an effective reduction in the order parameter, S which is defined by (P. G. deGennes, The Physics of Liquid Crystals, Clarendon Press, Oxford 1974):

$$S = \frac{1}{2} \left\langle \left(3\cos^2 \theta - 1 \right) \right\rangle$$

The order parameter is an indication of how well molecules align in a cell. Additionally the phase of the liquid crystal material at the surface may be changed by the oligomers, eg from nematic or long pitch cholesteric to isotropic.

The treatment may be used in conjunction with a surface which induces monostable pretilted nematic alignment.

The alignment layer may be a rubbed polymer surface as described in S. Ishihara et al, Liq. Cryst., vol.4, no. 6, p.669-675 (1989) or an obliquely evaporated inorganic material as described in W. Urbach, M. Boix and E. Guyon, Appl. Phys. Lett., vol. 25, no. 9, 479 (1974) or a polymer surface where in-plane anisotropy is achieved by illumination with polarised light such as M. Schadt et al, Jpn. J. Appl. Phys., v. 31, no.7, p. 2155 (1992).

Alternatively the alignment layer may be a surface monograting with an asymmetric groove profile as described in G. P. Bryan-Brown and M. J. Towler, "Liquid crystal device alignment", GB 2,286,466A (GB9402492.4).

The alignment directions on the two surface may be substantially perpendicular.

The nematic liquid crystal may contain a small amount (<5%) of a chiral dopant material e.g., R1011, CB15 Merck.

The cell walls may be substantially rigid e.g. glass material, or flexible e.g. polyolefin.

The electrodes may be formed as a series of row and column electrodes arranged and an x,y matrix of addressable elements or display pixels. Typically the electrodes are 200 µm wide spaced 20 µm apart.

5

10

Alternatively, the electrodes may be arranged in other display formats e.g. r-0 matrix or 7 or 8 bar displays.

In relation to bistable nematic devices, the present inventors have found that the problem of surface layer switching is reduced by using a surface treatment which changes the liquid crystal properties in the vicinity of the surface and so leads to a lower anchoring energy between the liquid crystal and the surface. This allows lower voltage operation without compromising other device parameters.

Accordingly, in a third aspect the invention provides a bistable nematic liquid crystal device which comprises; two cell walls enclosing a layer of nematic liquid crystal material; electrode structures on both walls; a surface alignment on both cell walls providing alignment direction to liquid crystal molecules; means for distinguishing between switched states of the liquid crystal material; CHARACTERISED BY means for reducing inelastic azimuthal memory anchoring energy in the surface alignment on one or both cell walls

Ideally the inelastic azimuthal memory anchoring energy is reduced to zero. Preferably the zenithal anchoring energy is also reduced.

25

The means for reducing energy may be an oligomer or short chain polymer which is either spread on the surface or added to the liquid crystal material.

Preferably the oligomer or short chain polymer does not change the pretilt by a substantial amount, e.g. change the pretilt by more than 5°.

The treatment is used in conjunction with a surface which induces bistable nematic alignment

The bistable surface may be a surface alignment bigrating on at least one of the cell walls that permits the liquid crystal molecules to adopt two different azimuthal alignment directions, as in patent application WO97/14990, (PCT-96/02463, GB95 21106.6).

The angle between the alignment directions may 90° or less than 90°.

The grating may be a profiled layer of a photopolymer formed by a photolithographic process e.g. M C Hutley, Diffraction Gratings (Academic Press, London 1982) p 95-125; and F Horn, Physics World, 33 (March 1993). Alternatively, the bigrating may be formed by embossing; M T Gale, J Kane and K Knop, J App. Photo Eng, 4, 2, 41 (1978), or ruling; E G Loewen and R S Wiley, Proc SPIE, 88 (1987), or by transfer from a carrier layer.

15

10

The bigrating may have a symmetric or asymmetric groove profile. In the latter case the surface induces both alignment and pretilt as described in GB2286467-A.

The gratings may be applied to both cell walls and may be the same or different shape on each wall.

The bistable surface could alternatively be formed by using an obliquely evaporated material as described in patent Application WO 92/0054 (G Durand, R Barberi, M. Giocondo and P Martinot-Largarde, 1991).

25

30

The cell walls may be substantially rigid e.g. glass material, or flexible e.g. polyolefin.

The electrodes may be formed as a series of row and column electrodes arranged and an x,y matrix of addressable elements or display pixels. Typically the electrodes are 200 µm wide spaced 20 µm apart.

Alternatively, the electrodes may be arranged in other display formats e.g. r-0 matrix or 7 or 8 bar displays.

In relation to smectic devices, the present inventors have found that problems in such devices may be reduced by use of a surfactant to lower the interaction between the surface(s) of cell wall(s) and the liquid crystal in the smectic phase, or in the overlying nematic phase from which the cell is cooled into the smectic phase for all operating temperatures. This use of a surfactant may be termed a slippery surface treatment. Thus improved alignment, optical properties, switching speed and stability to shock of smectic devices are achieved through slippery surface treatment.

Accordingly, in a fourth aspect the invention provides a smectic liquid crystal device which comprises: a liquid crystal cell including a layer of smectic liquid crystal material contained between two walls bearing electrodes and surface treated to give both an alignment and a surface tilt to liquid crystal molecules; CHARACTERISED BY means for reducing anchoring energy at the surface alignment on one or both cell walls.

The means for reducing anchoring energy may be an oligomer containing esters, thiols, and/or acrylate monomers and or which is either spread on the surface or added to the liquid crystal material.

20

25

5

In its most elemental form the surfactant provides a slippery surface which reduces the interaction between the liquid crystal molecules and those of the surface of the cell wall (or alignment layer surface). Thus, the slippery surface may be thought as having increased freedom for translational and rotational movement of the liquid crystal molecules closest to the surface. There are five surface terms (ref: Int Ferroelectric Liquid Crystal Conf (FLC95), Cambridge, UK, 23-27 July 1995, vol.178 No.1-4 J.C.Jones, pp155-165) which are relevant and may be controlled by the surfactant:

30 (1) α, zenithal anchoring energy. How easily the director surface tilt angle is changed (i.e. a rotational energy).

(2) β, azimuthal anchoring energy - case of changing surface twist angle of director (i.e. a rotational energy)

19

(3) y, related to the pretilt angle of the director at the surface

5

10

20

(4) Layer pinning term - How easily layers may be moved across the surface (i.e. a translational energy). This is the macroscopic effect of the (partial) adsorption of liquid crystal molecules onto the surface layer reducing translational movement of the molecules and hence of the smectic layers.

(5) Polar surface energy - In ferroelectrics (or flexoelectrics) a term which is minimum for a particular orientation of the Ps at the surface.

In this aspect of the present invention each of these factors is influenced by the presence of a slippery surfactant which acts to separate the solid and liquid crystal regions by the induced changes of liquid crystal order close to the surface. For example, if nematic order exists close to the surface layer of a smectic device, then layer pinning is greatly reduced. If the cone angle is lower surface switching is reduced as will the polar surface term.

Advantages provided by this aspect of the present invention are as follows:

- (I) Reduced layer pinning hence control of the smectic layers is easier;
- (2) Reduced nematic-like surface energies, hence orientation changes of the director at the surface are enhanced.
 - (3) Reduced adsorption of liquid crystal molecules at the surface, hence reduced surface memory effects and reduced surface viscosity;
- (4) Reduced polarity of the surface, hence less coupling to the spontaneous polarisation coefficient (Ps) in ferro electric liquid crystal systems resulting in less T state formation.

Specific embodiments of the invention will be described below, by way of example, with reference to the accompanying drawings, in which:

Figure 1 is a plan view of a matrix multiplexed addressed liquid crystal display;

Figure 2 is the cross section of the display of figure 1;

5

Figure 3 shows the configuration for photolithographic exposure leading to the formation of an asymmetric monograting useful in twisted nematic devices.

Figure 4 shows the transmission versus voltage data for two twisted nematic cells, one of which (dotted line) has been treated with an additive (Norland 65) to give weak 10 anchoring on asymmetric gratings.

Figure 5 shows the optical contrast ratio versus voltage data for two twisted cells, one of which (dotted line) has been treated with an additive to give weak anchoring.

15

Figure 6 shows transmission - voltage curves for two voltage controlled twist type cells, one with a standard alignment, the other with a weak anchoring energy treatment.

Figure 7 shows the configuration for photolithographic exposure leading to the formation of a bigrating with orthogonal grating modulations,

Figure 8 shows switching characteristics for two bistable cells, one with standard alignment, the other with a weak surface anchoring energy,

25

Figure 9 shows diagrammatically a smectic liquid crystal molecule, and how it moves within a layer when switched to its bistable states in a ferroelectric liquid crystal cell,

30

Figure 10 shows variation in memory angle against applied voltage for two bistable ferroelectric liquid crystal devices, one with standard alignment, the other with a weak surface anchoring energy.

21

Figure 11 shows the theoretical surface director tilt versus voltage for values of surface extrapolation lengths L.

Figure 12 shows the theoretical midlayer director tilt versus voltage for values of L

5

Figure 13 shows the transmission versus voltage data for two cells, one of which (dotted line) has been treated with an additive (MXM035) to give weak anchoring. Gratings have been used on both surfaces for alignment. Cell gaps are 2.05μm

Figure 14 shows the transmission versus voltage data for two cells, one of which (dotted line) has been treated with an additive (MXM035) to give weak anchoring. Gratings have been used on both surfaces for alignment. Cell gaps are 4.6μm.

Figure 15 shows the transmission versus voltage data for two cells, one of which (dotted line) has been treated with an additive (MXM035) to give weak anchoring. Rubbed polymer layers have been used on both surfaces for alignment. Cell gaps are 4.6μm.

Figure 16 is a diagrammatic view of a bistable ferro electric display with row and column drivers providing an x,y matrix display;

Figure 17 is a cross section of the display cell of Figure 16; and

Figure 18 is a schematic view of a layer of ferro electric liquid crystal material, showing two alignment configurations, the C₁ and the C₂ states.

The application of aspects of the present invention to twisted nematic, bistable nematic, and smectic devices will now be described in separate groups of examples.

30 Twisted nematic devices

The display in figures 1, 2 comprises a liquid crystal cell 1 formed by a layer 2 of nematic or long pitch cholesteric liquid crystal material contained between glass walls

22

3, 4. A spacer ring 5 maintains the walls typically 2-10µm apart. Additionally numerous beads of the same dimensions may be dispersed within the liquid crystal to maintain an accurate wall spacing. Strip like row electrodes 6 e.g. of SnO₂ or ITO are formed on one wall 3 and similar column electrodes 7 are formed on the other wall 4. With m-row and n-column electrodes this forms an m×n matrix of addressable elements or pixels. Each pixel is formed by the intersection of a row and column electrode. A row driver 8 supplies voltage to each row electrode 6. Similarly a column driver 9 supplies voltages to each column electrode 7. Control of applied voltages is from a control logic 10 which receives power from a voltage source 11 and timing from a clock 12.

10

15

30

Either side of the cell 1 are polarisers 13, 13' arranged with their polarisation axis substantially crossed with respect to one another. An additional optical compensator such as a stretched plastic film may also be added between the liquid crystal cell and one of the polarisers. A partly reflecting mirror 16 may be arranged behind the cell 1 together with a light source 15. These allow the display to be seen in reflection and lit from behind in dull ambient lighting. For a transmission device, the mirror may be omitted.

Prior to assembly, the cell walls 3, 4 are treated with alignment treatments to provide a monostable pretilted alignment. The alignment directions R1, R2 are shown as orthogonal to give a 90° or 270° twisted cell, but may be at other angles, e.g. at 45°. Finally the cell is filled with a nematic material which may be e.g. E7, ZLI2293 or MLC 6608 (Merck), and may include a chiral additive such as CB15 or R1011 (Merck).

In use the display may be multiplex addressed in a conventional manner by the application of a row waveform applied to each row in turn whilst applying waveforms to all columns. Such addressing is capable of applying two different rms value waveforms at each x,y intersection. One waveform has an rms value above a switching threshold and will therefore switch the liquid crystal material to an ON state. The other resultant waveform has an rms value below the switching threshold and therefore does not switch the liquid crystal material.

The number of x,y pixel elements that can be rms addressed is limited by the steepness of a device transmission verses voltage curve (as described by Alt and Pleshko in IEEE Trans ED vol ED 21, (1974) P.146 - 155). Therefore improvements to the steepness of the transmission - voltage curve are highly desirable. Additionally, if more of the material can be switched (switching the molecules adjacent a wall surface, rather than switching only at the layer centre) then a higher contrast between ON and OFF states would be obtained.

These nematic materials in embodiments of the invention contain the treatment or a precursor of the treatment which leads to a lowering of the anchoring energy.

In general, anchoring of a nematic liquid crystal on a surface can be described by three macroscopic parameters, pretilt, zenithal anchoring energy and azimuthal anchoring energy. Consider a surface in the x-y plane, parallel to the cell walls. The pretilt (θ_p) is defined as the preferred angle of inclination of the nematic director with respect to the x-y plane. To change the tilt of the surface director from θ_p to an arbitrary tilt θ , an energy per unit area of W must be supplied to the system where [A. Rapini and M. Papoular, J. Phys. (Paris), 36, C-1, 194 (1975)]:

20

15

5

$$W = W_{\theta} \sin^2(\theta - \theta_{\rho}) \tag{1}$$

We is the zenithal anchoring energy and represents the energy required in order change the tilt of the surface director by 90°. If the director has a preferred in-plane orientation, say along the x axis, then an energy must be supplied to the system to change this orientation. The energy is now given by

$$. W = W_{\phi} \sin^2 \phi \tag{2}$$

where ϕ is the change in the in-plane orientation and W_{ϕ} is the azimuthal anchoring energy.

24

Pretilt and zenithal anchoring can be achieved from most solid surfaces while azimuthal anchoring usually requires some extra treatment in order to obtain a preferred in-plane direction such as an anisotropic polymer, obliquely evaporated film or a surface grating. For most surfaces W_{θ} and W_{ϕ} are large and so reorientation of the director at the surface only occurs at high voltages.

5

25

The effect of the weak zenithal anchoring on a twisted nematic device is discussed below.

The improvement in operation of a 90° twisted nematic cell with weak surface anchoring was first analysed theoretically. The static configuration of the cell was calculated by minimising the total free energy which is dictated by the Eular-Lagrange equation in the bulk and by equations (1) and (2) at the surfaces. The zenithal anchoring energy W_{θ} was then relaxed from its usual large value and the effect on the static configuration was calculated. Figure 3 shows several curves calculated for different surface extrapolation lengths, L where $L = k_{11}/W_{\theta} \cdot d$. The parameters common to all the curves are;

 $k_{22}/k_{11} = 0.6$; $k_{33}/k_{11} = 1.5$; $\epsilon_{para} = 14.0$; $\epsilon_{per} = 4.0$; Cell twist = 90°; Surface pretilt = 5°

The reduced voltage is defined as the voltage which has been normalised by the Frederiskz threshold voltage (= $\sqrt{k_{11}/\varepsilon_0}\Delta\varepsilon$). Figure 11 shows the surface tilt angle as a function of applied voltage. For infinite zenithal anchoring energy (L=0.0) the tilt remains fixed at the zero volt pretilt value. However for finite anchoring (L>0) all the curves show that the surface director is reoriented by the applied field and shows an increasing tilt angle with voltage. It is expected that this voltage induced tilt will lead to a better contrast ratio in a typical normally-white twisted nematic device.

Figure 12 has been calculated with the same parameters as figure 11 but now shows the voltage dependent tilt in the middle of the nematic layer. This tilt angle is the dominant parameter in dictating the optical transmission of the twisted nematic

25

device. Therefore it is clear to see that a surface offering a finite L will lead to a lower voltage, steeper electrooptic response.

Therefore the above modelling has shown that a surface treatment which lowers W_{θ} will lead to a twisted nematic device which has a lower voltage threshold, a steeper electrooptic response and a higher contrast at a given voltage

Example TN1

15

An example of a weak anchoring treatment applied to a twisted nematic is now given.

The pretilted alignment surface used in this example was an asymmetric monograting as described in GB 9402492.4; GB-A-2,296,466; WO-95/22078.

The treatment consists of adding a small (1-10%) amount of a UV curing adhesive material to the nematic prior to cell filling. Examples of suitable materials include N65, N63, N60 or N123 (All manufactured by Norland Products Incorporated, North Brunswick, NJ, USA). In this particular example, one of these materials (N65) is used as an additive to the nematic E7 (Merck). This material contains a mixture of esters and acrylate monomers which polymerise under UV radiation.

Before using the N65 additive in a twisted nematic device a set of experiments were carried out in order to show the effect of the N65 treatment on the zenithal anchoring energy, Wθ. This quantity can be calculated by measuring the saturation voltage, V_S. That is, the voltage at which the director tilt in the cell is perpendicular to the surface throughout the thickness of the cell. This can be measured in cells where the surfaces have no preferred alignment direction. In this case flat surfaces of hardbaked photoresist were used (Shipley 1805). This material was spin coated on ITO coated glass to form a 0.55μm thick layer. Baking at 160°C for 45 minutes ensured full insolubility in the liquid crystal. When filled with N65/E7 mixtures, these cells show a random Schlerien texture. The saturation voltage was measured by observing when
 the transmitted intensity of the Schlerien texture falls to zero when viewed between crossed polarisers. Wθ is then given by

$$W_{\theta} \approx \frac{3.85\sqrt{\varepsilon_o \Delta \varepsilon k_{11}} \cdot V_s}{d} \tag{4}$$

where d is the liquid crystal thickness, k_{11} is the liquid crystal splay elastic constant and $\Delta \epsilon$ is the liquid crystal permittivity anisotropy.

Results are shown in table 1. The pure E7 cell failed to show a black state before cell breakdown and so only a lower limit on W_{θ} can be given. In the cases of the E7 containing N65, the curing was performed in a fused silica cell for 10 minutes prior to transferring the mixture to a separate measurement cell. The exposure was carried out using an unfiltered mercury lamp with an optical output of 2.0mW/cm^2 at a raised temperature of 65°C.

Cell mixture	W _θ (N m ⁻¹)	
Pure E7	>5×10-2	
2% N65 in E7	6.3×10 ⁻³	

Table 1

Surface zenithal anchoring energies modified by the presence of N65.

15

5

10

The above results clearly show that the N65 has reduced the value of W_{θ} in a cell with flat surfaces. The next step is to study the effect of this additive on the operation of a twisted nematic device.

Such a twisted nematic device may employ asymmetric monogratings to induce pretilted alignment and be fabricated in the following way as shown in Figure 3: Shipley 1805 photoresist 20 was spin coated at 3000 rpm onto ITO coated glass 21 for 30 seconds. Next the photoresist layer 20 was baked at 90°C for 30 minutes to remove the solvent. Exposure of the photoresist through a mask 22 was carried out using off axis hard contact photolithography. The mask 22 consisted of a chrome on glass pattern with a pitch of 1µm (0.5µm gaps and 0.5µm chrome strips). The exposure time was set to 540 seconds with an incident power of 0.15 mW/cm² from a mercury

lamp. Development was then carried out in Shipley MF319 for 10 s followed by a water rinse. Samples were finally baked at 160°C for 45 minutes after first receiving a deep UV exposure to preharden the photoresist (3.36 J/cm² at 254nm).

27

- The above process resulted in a surface monograting with a 1μm pitch and a 0.5μm peak to trough groove depth. The profile is asymmetric (approximately sawtooth in form) which leads to a pretilted alignment if the nematic is under the influence of a bulk twist torque (see GB-A-2,296,466; WO-95/22078). These surfaces were constructed into cells in which the groove direction on one surface was orthogonal to the groove direction on the other. The cell gap was set to 2.05μm which corresponds to the first Gooch and Tarry minimum when used with E7 (J. Phys. D. Appl. Phys. vol. 8, p. 1575 (1975)). Filling was then carried out using E7 in the isotropic phase (65°C) followed by slow cooling to room temperature.
- The electrooptic response of cells containing different N65/E7 mixtures was then recorded by placing the twisted nematic cell between crossed polarisers which were oriented parallel to the adjacent grating alignment directions. Transmission was measured using a photodiode with a photo-optic response during the application of a 1kHz sinusoidal drive waveform. Figure 4 shows the transmission versus rms voltage for two cells one of which was treated to give weak anchoring. The weak anchoring treatment consisted of adding 2% N65 to E7 and curing for 10 minutes in a pre-cell before transferring the material to the test cell. The data clearly shows that the weak anchoring treatment has lowered the operating voltage. A transmission of 50% of the zero volt value is reached at a voltage of 1.83 V for the weak anchored surface and 2.13 V for the strong anchored surface. The power consumption of a display can be considered in the most simple case as the power required to charge and discharge a capacitor which is proportional to V2. Therefore the weak anchored surface is expected to allow a power saving of roughly 35%.
- The second improvement of the weak anchored cell is the improved optical contrast ratio as shown in figure 5. At 5 V the weak anchored cell has a contrast ratio of 126 while the strong anchored cell has a contrast ratio of 49. At 8 V the difference is even

28

larger (410 and 74 respectively). Therefore if a particular application demands a certain contrast ratio then it can be reached at a much lower voltage with a weak anchored surface. The weak anchoring has also lead to a slight increase in the steepness of the electrooptic response. For the weak anchored surface V₉₀ - V₅₀ is 0.454 V while for the strong surface this quantity is 0.510 V; V₉₀ and V₅₀ being the voltage at transmissions of 90% and 50% of the zero voltage transmission value respectively.

In summary the above experimental results have shown qualitative agreement with the theoretical analysis by demonstrating that a surface which has been treated to give a lower W_{θ} can improve a twisted nematic device. The improvements include a lower voltage threshold, a steeper electro optic response and a higher optical contrast.

Example TN2

15

20

25

30

10

In this example MXM035 (Merck) was used as the weak anchoring treatment. The alignment surfaces were asymmetric monogratings as described in example TN1.

The MXM035 consists of two parts which were mixed in equal quantities. This mixture was then added to E7 nematic to give a 4% solution which was cured in a fused silica cell (as described in example TN1) before transferring to a test cell. A measurement of W_{θ} for the 4% solution revealed a value of $3.85 \times 10^{-4} \text{J/m}^2$. This is 16 times smaller than the value of measured for N65 (in example TN1). Therefore the MXM 035 treatment is expected to have a larger effect on the operating behaviour of a TN device.

Cells were constructed using asymmetric monogratings as alignment surfaces. The groove direction on one surface was orthogonal to that on the other to ensure a twisted configuration with a liquid crystal twist of roughly 90°. The cell gap was set to 2.05µm (the first Gooch and Tarry minimum). Figure 13 shows the transmission versus rms voltage for two cells, one of which was treated with 4% MXM035 to give weak anchoring. In this case the weak anchoring treatment has lead to a very large

decrease in operating voltage. A transmission of 50% of the zero volt value is reached at a voltage of 0.8 V for the weak anchored surface compared to 1.93 V for the strong anchored surface. Hence the weak anchored TN is expected to use only 17% of the operating power of a conventional TN.

5

10

15

Weak anchoring treatments can also lead to improvements in performance when the cell gap is larger. To demonstrate this, data was taken from two more TN cells which had been constructed with a cell gap of 4.6 μ m which corresponds to the second Gooch and Tarry minimum for E7. One of these was filled with pure E7 while the other was filled with 4% MXM035 in E7 which had been precured as described above. Figure 14 shows the electrooptic response for these two cells. Once again the weak anchored cell shows a response at a much lower voltage. The 50% transmission occurs at 1.07 V for the weak anchored TN compared to 2.16 V for the conventional TN. The weak anchoring treatments are expected to change the dynamic response of the TN and so optical response times were measured for these cells for switching between 0 V and 4V as shown in table 2. It can be seen that the addition of MXM035 has lead to a decrease in switch-on time (τ_{on}) and an increase in switch-off time (τ_{off}). This behaviour is consistent with weak surface anchoring.

Cell Mixture	ton (ms)	τ _{offee} (ms)
E7	6.8	15.5
E7 + 4%MXM035	2.5	24.0

20

Table 2

0-4 V optical switching times for second minimum TN cells with strong or weak anchoring.

25 Example TN3

Weak anchoring treatments can also be used in conjunction with other surface alignments to improve TN performance. In this example the MXM035 treatment is used in conjunction with a rubbed polymer alignment.

30

Rubbed alignment surfaces were prepared by spin coating a layer of probomide 32 (Ciba Geigy) onto ITO coated glass and baking the substrates at 300°C. The surfaces were then rubbed in one direction by a nylon cloth attached to a rotating roller. Finally cells were constructed in which the rubbing direction on one surface was orthogonal to that on the other. The cell gap was set to 4.6µm using monodispersed spacer beads in the edge seal. Figure 10 shows a comparison of electrooptic responses recorded from two TN cells, one filled with E7 and the other filled with E7+ 4% MXM035. Once again the addition of the weak anchoring treatment has lead to a reduction in operating voltage.

10

Example TN4

One particular type of twisted nematic device is the VCT device, which switches from a substantially non-twisted state to a twisted state when a voltage is applied. In this example the operation of the VCT device is improved by the addition of a weak anchoring treatment. The surface alignment in this example was provided by asymmetric grating surfaces as described in example TN1.

The weak anchoring treatment was MXM035 mixed from 10 % of part A and 90% of part B. 4% of this mixture was added to nematic MLC 6608 which has a negative dielectric anisotropy. The MXM035 was then cured by placing the MXM035/MLC6608 mixture in a glass cell and exposing to UV radiation (10 minutes at 2.0mW/cm² while at a temperature of 65°C). After curing the mixture was used to fill a VCT test cell.

25

30

The VCT cells were constructed so that the grating grooves on one surface were orthogonal to those on the other. Prior to construction the grating on one surface was treated with a chrome complex surfactant in order to induce a homeotropic boundary condition (molecules perpendicular to the wall surface). The grating on the other surface was left untreated in order to induce a planar boundary condition. The cell gap was set to 5.3 µm using spacer beads in the edge seal. Figure 6 shows the electrooptic response of two VCT devices, one of which contains the weak anchoring treatment. The VCT containing pure MLC6608 exhibits 50% transmission at a voltage of 2.91 V

31

while the VCT containing 4% MXM035 in MLC 6608 exhibits 50% transmission at a voltage of 1.52 V. Therefore the weak anchoring treatment has lead to a dramatic decrease in operating voltage.

The dynamic response times of the VCT were measured for these cells for switching between 0 V and 5V as shown in table 3. It can be seen that the addition of MXM035 has lead to a decrease in switch-on time (τ_{on}) and an increase in switch-off time (τ_{off}).

Cell Mixture	τ _{on} (ms)	τ _{offee} (ms)	
MSc 6608	86	60	
MSC 6608	+60	112	
4%MXM035			

10 Table 3

15

20

25

0-5 V optical switching times for VCT cells with strong or weak anchoring.

The above examples show that the addition of oligomeric materials (Norland 65, MXM035) into cells with either grating surfaces or rubbed polymer surfaces will lead to a reduction in the operating voltage of a twisted nematic device.

Bistable Nematic Devices

These have substantially the same basic construction as shown in Figures 1 and 2, with certain differences. The input polariser is parallel to one alignment state for the case where the alignment states differ in azimuthal angle by 90°. The most significant practical difference is that at least one of the cell walls 3, 4 are treated with alignment gratings to provide a bistable alignment (rather than a monostable alignment as for the twisted nematic case), i.e. two stable alignment directions shown as R,R' 45° apart, but may be 90°. For example the alignment may be provided by a bigrating with symmetric and asymmetric profiles to give both alignment and a required amount of pretilt. Techniques for producing bigratings to give bistable nematic devices are described in GB-A-2,286,467 (PCT-WO-95/22077) and WO97/14990, (PCT-96/02463, GB95 21106.6).

25

30

The second surface of the cell (if not provided with a bigrating) may be treated with either a planar or homeotropic monostable surface.

Conventional alignment techniques provide pretilt (zenithal) and alignment direction (azimuthal) with substantial anchoring energy. This means that switching of the device under the influence of electric fields results in movement of the liquid crystal molecules mostly in the centre of the layer, and zero movement at and adjacent the wall surface. Both pretilt and alignment direction are necessary for good device performance. What is wanted is pretilt values and alignment together with reduced anchoring energy so that molecules at or adjacent the cell walls can move under the application of normal voltage levels.

Embodiments of the present invention provides such a wanted pretilt and alignment together with lowered surface anchoring energy. The invention does this, in one embodiment, by inclusion of oligomer units in the liquid crystal layer 2 and which preferentially migrate to the cell wall surfaces.

Bistable nematic switching relies on surface director reorientation and in order to achieve low voltage switching both the zenithal and azimuthal anchoring energies must be reduced.

Furthermore any additional inelastic memory azimuthal anchoring (P. Vetter et al, Euro Display 1993, SID, p.9) due to microscopic absorption of the first nematic layer into the surface must be removed. This anchoring memory may have the effect of pining molecules in a given position (e.g. between the two switched states) to which they may return after removal of a voltage. Ideally this memory should be completely removed so that the molecules remain in their switched positions after removal of voltages. In practice, reduction rather than complete removal can be satisfactory.

Three examples of the weak anchoring treatment applied to a bistable surface are now given:

Example BN1

The treatment consists of adding a small (1-10%) amount of a UV curing adhesive material to the nematic prior to cell filling. Examples of suitable materials include N65, N63, N60 or N123 (All manufactured by Norland Products Incorporated, North Brunswick, NJ, USA). In this particular example, one of these materials (N65) is used.

In the first experiment this material was added to nematic E7 in concentrations of 1%, 2%, 4% and 6%. The mixture was then used to fill cells whose inside walls were coated with flat polymer layers, without any alignment direction. The purpose of this experiment was to confirm a weakening of the surface anchoring with the addition of N65. Surfaces were prepared using a layer of photoresist (Shipley 1805) which was hardbaked to 160°C to ensure insolubility in the liquid crystal.

15

20

25

30

10

Cells were made using these surface with a gap of 10µm. Each was filled with a different concentration of N65 including a control sample of pure E7. Filling was carried out in the isotropic phase (65°C) followed by slow cooling to room temperature, and without exposure to UV light. All cells showed a random planar alignment of the nematic which is also called a Schlerien texture. In the case of the pure E7, 1% N65 and 2% N65, the texture could not be moved by applying finger pressure to the cell walls whereas for the 4% and 6% mixtures, the texture was highly mobile and domain walls could be easily moved by applying small amounts of pressure. Once the domain walls had been moved they did not return to their original position but instead remained in the new position for longer than several days. Therefore the 4% and 6% mixtures lead to a loss of memory anchoring.

A second similar experiment was carried out in which the cells were exposed to UV radiation after filling but before cooling to room temperature. In this case the 4%, 6% and also the 2% mixtures showed room temperature domain wall mobility. The improvement in the 2% mixture can be explained as follows. The N65 material contains both esters and acrylate monomers which polymerise under UV radiation to form oligomer units which then join together to form larger polymer chains. If the 2%

34

solution is cured for a short time then the reaction can be terminated when only oligomer units have been formed. The oligomers do not phase separate from the liquid crystal but they so migrate preferentially to the surface in order to minimise the surface free energy. This has the effect of diluting the amount of liquid crystal at the surface which leads to an effective reduction in the order parameter, S which is defined by (P. G. deGennes, The Physics of Liquid Crystals, Clarandon Press, Oxford 1974):

$$\dot{S} = \frac{1}{2} \left\langle \left(3\cos^2 \theta - 1 \right) \right\rangle \tag{3}$$

10

15

20

The reduction in nematic order due to a oligomer concentration has the twofold effect of screening the liquid crystal from the surface which removes the memory anchoring as well as reducing the elastic anchoring energy, W₀. The uncured material also has this effect but must be added in a greater concentration (>4%) as the acrylate monomer does not preferentially migrate towards the surface.

The cured material containing 2% N65 was then removed from the cell in which it was cured and used to fill another cell. This second cell also showed a highly mobile Schlerien texture demonstrating that the weak anchoring effect is due to the additive in the bulk as opposed to any surface layer formed during curing.

The next set of experiments were designed to show the effect of the N65 treatment on the zenithal anchoring energy, W_{θ} . This quantity can be calculated by measuring the saturation voltage, V_{S} as described in example TN1.

25

30

Results are shown in Table 4. The pure E7 cell failed to show a black state before cell breakdown and so only a lower limit on W₀ can be given. In the cases of the E7 containing N65, the curing was performed in a fused silica cell prior to transferring the mixture to a separate measurement cell. The exposure was carried out using an unfiltered mercury lamp with an optical output of 2.0mW/cm².

Cell mixture	Cure time (m)	W _θ (N m ⁻¹)
rure E7	-	>5×10 ⁻²
2% N65 in E7	5	5.4×10 ⁻³
% N65 in E7	10	6.3×10 ⁻³
% N65 in E7	30	7.7×10 ⁻³
2% N65 in E7+ pure E7 (1:1)	10	8.0×10 ⁻³

Table 4

Surface zenithal anchoring energies modified by the presence of N65.

Greater cure times are found to lead to stronger anchoring which is consistent with the formation of longer polymer chains which tend to phase separate from the nematic rather than lower its surface order parameter. One set of data shows that the anchoring energy can also be adjusted by diluting the N65/E7 mixture in pure E7. In all cases the percentage of N65 during the cure process was kept to 2% to ensure consistent reaction kinetics.

10

The above results confirm that the N65 treatment leads to a loss of in-plane memory anchoring as well as lowering (by about an order of magnitude) the zenithal anchoring energy. The next stage is to test the effect of the treatment on the switching of a bistable nematic device.

15

20

One example of a surface which can offer bistable nematic alignment is a surface bigrating (as described in GB2286467-A.) prepared in a manner similar to that shown in Figure 7. In this case samples were made by spin coating 1805 photoresist 20 onto ITO coated glass 21 at a spin speed of 3000 rpm to give a coating thickness of 0.55 \mum. The samples were then softbaked at 90°C for 30 minutes. The bigrating was exposed through a mask 22 using hard contact photolithography (i.e. normal to the mask 22 surface, not at 60° as in Figure 7) with a typical exposure time of 250s (at 0.3 mW/cm²). The mask 22 contained a bigrating pattern of 0.9 \mum chrome squares separated by 0.5 \mum gaps in each direction giving a pitch of 1.4x1.4 \mum. Development was then carried out in Shipley MF319 for 10 sec followed by a water rinse. Samples

36

were finally baked at 160°C for 45 minutes after first receiving a deep UV exposure to preharden the photoresist (3.36 J/cm² at 254nm). This process created a bigrating with two identical modulations each of which had a symmetric profile. The alignment of a nematic on this is therefore expected to consist of two non tilted alignment states (alignment, but no surface tilt) separated by an azimuthal angle of 90°. Such an alignment is not normally of use in display devices, but was prepared for test and comparison purposes.

Cells having a cell gap of 0.95µm were then made with these (zero pretilt) bigratings on both inner surfaces arranged so that the groove directions on one surface coincided with the groove directions on the other. These were filled with E7 nematic containing various concentrations of N65 in its isotropic phase. On cooling to room temperature all cells showed two alignment directions as expected. As the states have no surface pretilt, and hence no splay, there is no method (like the flexoelectric coupling in splayed configurations) by which only one state can be selected using applied electrical pulses. However random switching between the states can occur which was seen by pulse-induced domain wall movement.

10

15

20

25

Rectangular monopolar pulses of various pulse lengths were applied to each cell. Each pulse alternated in sign from the previous pulse to maintain a dc balance. Pulses were separated by a time interval 100 times the pulse length. For each pulse length a voltage existed above which domain wall movement occurred. Figure 8 shows this threshold voltage versus time for two cells; one a cell filled with pure E7, and the other a cell filled with a 2% precured mixture of N65 in E7. The N65 has clearly lowered the voltage threshold to a value of only 5.0 V/µm for a 10.8 ms pulse. In contrast the pure E7 cell shows a much higher voltage switching (15.0 V/µm) and in fact suffered dielectric breakdown for low pulse lengths.

The above results show that the N65 treatment leads to a low voltage bistable switching which is consistent with a low zenithal anchoring energy combined with no in-plane memory anchoring other than the elastic W_b imposed by the bigrating.

In order to obtain fully selective bistable switching one state has to be favoured by the applied pulse. This can be achieved using dc coupling to a flexoelectric polarisation if the two bistable states have the appropriate pretilts. In WO 92/0054, pretilt can be obtained by using obliquely evaporated SiO.

5

10

15

A more controllable method, described in GB2286467-A achieves pretilt by using a bigrating in which both modulations have asymmetric profiles. This method allows a pretilt of typically 17° for one of the bistable states while maintaining a pretilt of 0° for the other state. These surfaces were tested in conjunction with the N65 treatment using the following fabrication process as illustrated in Figure 7.

A thin layer 20' of 1805 photoresist was spun onto ITO coated glass 21' as described above. After softbaking, the layer 20' was exposed through the 1.4x1.4μm pitch mask 22' using an off axis diagonal exposure geometry as shown in figure 7; i.e. exposure at about 60° to the surface normal and about 45° to the mask array of square pixels. The exposure time was set to 540 seconds (at 0.15 mW/cm²). After development and processing the bigrating was constructed opposite a flat photoresist surface (i.e. no grating and hence zero pretilt) using 10μm cell spacers to allow measurement of the surface pretilt at the bigrating surface.

20

Table 5 shows the pretilt of the tilted state measured by the crystal rotation method (T. J. Scheffer and J. Nehring, J. Appl. Phys., vol.48, no. 5, p. 1783 (1977)) for cells filled with various mixtures. In all cases the non-tilted state had a pretilt of less than 0.1°.

25

Mixture used to fill cell	Pretilt (°)	
Pure E7	17.5	
2% N65 in E7+ pure E7 (1:1)	17.1	
2% N65 in E7+ pure E7 (2:1)	15.4	
2% N65 in E7	2.2	

Table 5.

Surface pretilt modified by the presence of N65.

The pure E7 gave a high pretilt as expected but the addition of 2% N65 (precured) lead to a catastrophic loss of pretilt which means that this treatment is not suitable for a flexoelectric coupled device where a significant pretilt is required in order to achieve dc sensitivity. However further diluting of the 2% mixture via addition of pure E7 allows the pretilt to be at a value close to the pure E7 cell.

Comparison of data in table 4 and table 5 shows that it is possible to obtain a mixture regime which provides weak zenithal anchoring while maintaining surface pretilt. The loss of pretilt for 2% N65 in E7 can be understood by the further weakening of W₀ which allows the nematic to adopt a non tangential orientation with the local surface. This destabilises the high pretilt state with respect to the low pretilt state. Such states are described in GB9502635.7, "liquid crystal device alignment", G. P. Bryan-Brown, C. V. Brown and D. G. McDonnell.

15

10

5

The above results have shown one example of how an oligomeric additive (N65) can be mixed with a typical nematic (e.g. E7) to improve the voltage response of a bistable nematic device without compromising other surface parameters such as pretilt.

20

25

Example BN2

Another example of a weak anchoring treatment was synthesised using block polymerisation of a thiol and a vinyl ether to form the structure A shown below, the subscript n is number of repeats in a chain.

As in example BN1, the precursor materials were added to E7 and then cured in a fused silica pre-cell. The cured mixture was then transferred to a second cell whose inner surfaces were coated with hardbaked photoresist. Filling was carried out at 65°C followed by slow cooling to room temperature. One particular cell was filled with a

39

mixture which had been cured from a 5% solution of the precursor materials in E7. This cell showed a schlerien texture with highly mobile domain walls confirming that all in-plane memory anchoring had been lost.

A measurement of the saturation voltage revealed that the zenithal anchoring energy had been lowered to a value of 1.2x10⁻³ N m⁻¹. This is even lower than the values shown in table 4 which indicates that the oligomer units formed in this case are more effective at lowering the surface order parameter of the nematic phase. Once again dilution of the 5% solution into pure E7 revealed a regime on grating surfaces in which weak zenithal anchoring was combined with high (>15°) pretilt.

Therefore the structure A is another successful example of an oligomer which can be added to a nematic (e.g. E7) improve the voltage response of a bistable nematic device without compromising other surface parameters such as pretilt.

15

Example BN3

The following structures B is a list of example monomers which can also be used to created weak anchoring treatments.

20

$CH_2 = CH O(CH_2)_6 O CH = CH_2$	HDVE (Hexane -1,6-diol di(vinyl ether)	В
CH ₂ =CHOC ₄ H ₉	BVE (Butyl vinyl ether)	B
HSCH ₂ CO ₂ (CH ₂) ₂ OCOCH S ₂ H	EGTG (Ethylene glycol bis(thioglycollate	e)) B
HS(CH ₂) ₉ SH	NDT (Nonane-1,9-dithiol)	B

25

In previous examples low voltage bistable nematic switching has been shown to occur when W_q is lowered. Therefore the materials in B have been investigated to determine their effect on W_θ .

Mixtures of these materials were cured before adding to the liquid crystal and the final mixture was tested in cells containing flat hardbaked photoresist on the inner surfaces

as described in example BN1. Values of W_{θ} were then obtained using the method described in example BN1.

Of the materials listed, EGTG and NDT are monomers with thiol terminations while HDVE and BVE are diffunctional and monofunctional '-ene' materials respectively.

The first set of mixtures studied are shown in table 6. In each case a percentage of monfunctional BVE has been added to the bifunctional HDVE in order to induce chain termination and so form oligomers with smaller molecular weights. In each case the quoted percentage is the molar quantity of BVE with respect to HDVE. Furthermore the quantity of NDT in each mixture was varied to maintain an equal number of thiol groups and ene groups. To each mixture was added 1% of Igracure 651 (Merck) which acts as a photoinitiator. For each material, curing was carried out under a mercury lamp (2.0 mW/cm²) for 10 minutes. E7 (Merck) was used as the liquid crystal to which was added 2% of each material (by weight). The results in table 6 shows that the resulting zenithal anchoring energy (W₀) lies in the range 3.6-8.8×10⁻³ J m⁻². Therefore all the mixtures can be considered to be successful in reducing the anchoring from the value found for pure E7 (>5×10⁻² J m⁻²). Furthermore addition of more BVE and hence shorter oligomer chains is found to lead to weaker anchoring.

Material	$W_{\theta} \times 10^{-3} \mathrm{J m}^{-2}$	
NDT/HDVE/2% BVE	8.8	
NDT/HDVE/5% BVE	5.9	
NDT/HDVE/20% BVE	3.6	

Table 6.

Measurement of zenithal anchoring for thiol/diene systems with chain termination.

25

5

15

20

The correlation of anchoring and molecular length for a given material type was further tested using a set of mixtures containing EGTG, HDVE and BVE. In this case GPC analysis was carried out in order to measure the molecular weights of each

41

material as shown in table 7; Mn is number average of each chain, Mw is average weight per chain, and W_{θ} is zenithal anchoring energy. The smallest portion of BVE (2%) is indeed found to lead to the longest molecular weights and vice versa. 1% of each of these materials was added to E7 and W_{θ} was measured. The correlation of W_{θ} with molecular weight is fairly good considering the errors in the W_{θ} measurement.

Material	Mn	Mw	$W_{\theta} \times 10^{-3} \text{ J m}^{-2}$
EGTG/ HDVE / 2% BE	12640	27330	10.9
EGTG/HDVE/5% BE	6970	17140	5.3
EGTG/HDVE/10%BE	5000	11550	6.6
EGTG/ HDVE / 20% BE	2900	6200	4.4

Table 7.

Measurement of zenithal anchoring for thiol/diene systems with chain termination.

To summarise, in this example two sets of materials have been studied both have been found to lead to a reduction in W_{θ} . Furthermore samples of these materials have also been found to reduce the switching voltages in bistable nematic devices.

Smectic Devices

10

15

20

25

The display cell 101 shown in Figures 16, 17 comprises two glass walls 102, 103 spaced about 1-6 µm apart by a spacer ring 104 and/or distributed spacers.

Electrode structures 105, 106 of transparent tin oxide are formed on the inner face of both walls. These electrodes are shown as row and column forming an X, Y matrix but may be of other forms. For example, radial and curved shape for a polar coordinate display, or of segments form for a digital seven bar display, or plain sheet electrodes to form an optical shutter.

42

A layer 107 of smectic liquid crystal material is contained between the walls 102, 103 and spacer ring 104.

Polarisers 108, 109 are arranged in front of and behind the cell 101. Row 110 and column 111 drivers apply voltage signals to the cell. Two sets of waveforms are generated for supplying the row and column drivers 110, 111. A strobe waveform generator 112 supplies row waveforms, and a data waveform generator 113 supplies ON and OFF waveforms to the column drivers 111. Overall control of timing and display format is controlled by a control logic unit 114.

10

15

30

5

Prior to assembly, the walls 102, 103 are surface treated by spinning on a thin layer of polymeric material such as polyimide or polyamide, drying and where appropriate curing; then buffing with a soft cloth (e.g. rayon) in a single direction R_1 , R_2 . This known treatment provides a surface alignment for liquid crystal molecules. In the nematic and cholesteric phases and in the absence of an applied electric field the molecules at the surface walls 102, 103 align themselves along the rubbing direction R_1 , R_2 and at a pretilt angle ξ of about e.g. 2° to 10° to the surface.

The surface alignment treatment is arranged to provide the required value of pretilt ξ . For example the material polyimide (e.g. Polyimide 32) when rubbed gives a typical pretilt of about 2°; the actual value depends upon liquid crystal material and the processing. Alternatively, as described in GB-A-2,286; GB-A-2,286,467; GB-A-2,286,894; GB-A-2,2986,893, the cell walls may have formed thereon grating structures which provide a range of pretilt angles and alignment directions. The gratings may be symmetric and/or asymmetric in profile, and shaped to give any desired value of pretilt ξ , and azimuthal and zenithal anchoring energies β , α respectively.

The device may operate in a transmissive or reflective mode. In the former light passing through the device e.g. from a tungsten bulb 115 is selectively transmitted or blocked to form the desired display. In the reflective mode a mirror 116 is placed behind the second polariser 109 to reflect ambient light back through the cell 101 and

43

two polarisers. By making the mirror 116 partly reflecting the device may be operated both in a transmissive and reflective mode.

Pleochroic dyes may be added to the material 107. In this case only one polariser is needed and the layer thickness may typically be 4-10µm.

5

15

20

25

If the smectic material 107 is a chiral smectic e.g. smectic C (S_C*) then a bistable device can be made. Such a device is the surface stabilised ferroelectric device (SSFLC) supporting two bistable states which are optically distinct. In a chiral smectic material molecules tend to lie and move along the surface of an (imaginary) cone as shown in Figure 9. When the surface alignment directions R1, R2 are parallel the (z) axis of these cones are parallel to these alignment directions and the molecules lie either side of the axis on the cone surface.

In one switched state D1 the molecules lie on one side of the cone, and in the second bistable state D2 lie on the other side of the cone. The switching is achieved by application of a voltage pulse of appropriate sign and length applied through the electrodes 106, 107 coupling with a spontaneous polarisation coefficient Ps of the material. The cone angle, θ_c , is a function of material parameters. In devices the molecules in their two switched positions D1, D2, do not lie on the extremities of the cone but some small distance away. This means that the angle between the bistable positions is somewhat less than the cone angle, and can be increased a bit by application of an ac voltage signal to the material; this is known as ac stabilisation mentioned above. Ideally the angle between the switched states is 45° because this would allow maximum contrast for the cell when arranged between crossed polarisers 108, 109 with the axis of one polariser along one of the switched directions. This gives a dark state in one switched position and a light state in the other switched position.

30 The angular distance between the two state is defined as the memory angle, θ_m (see N. Itoh et al, Jpn. J. Appl. Phys., 31, L1089 (1992)). The optimum memory angle for maximum brightness in the light state is therefore 45°. However most materials

44

possess a memory angle which is much less than 45° and so suffer from loss in brightness.

A weak anchoring treatment can be added to a ferroelectric to increase the memory angle and so improve the display brightness. This treatment also allows small amounts of translational movement of microlayers formed during cooling from isotropic phases to smectic phases leading to improved alignment.

Example of cell preparation.

10

15

Alignment surfaces were prepared by spin coating a layer of probomide 32 (Ciba Geigy) onto ITO coated glass and baking the substrates at 300°C. The surfaces were then rubbed in one direction R by a nylon cloth attached to a rotating roller. Finally cells were constructed in which the rubbing direction R₁ on one surface was parallel to that R₂ on the other. The cell gap (d) was set to 1.1µm using monodispersed spacer beads in the edge seal. Each cell was then filled with ZLI 5014 (Merck) ferroelectric liquid crystal doped with small percentages of N65. Before filling the N65 was cured in a separate cell.

Figure 10 shows the memory angle measured from two cells containing either pure ZLI 5014, or 4% N65 in ZLI 5014 as a function of applied voltage (50kHz AC). The results clearly show that the weak anchoring treatment has lead to a significant increase in memory angle at all voltages. Therefore the treatment has improved this ferroelectric device by increasing the on state transmission between crossed polarisers. For example at 5 V, the memory angle has increased from 17.1° to 34.4° which would lead to a device which is 3.7 times brighter.

Bistable ferro electric devices switch upon receipt of a unidirectional pulse of appropriate direction, amplitude, and length. Strobe pulses are applied sequentially down the rows, whilst one of two different data pulses are applied to each column. Examples of addressing are described in USP-5,497,173, GB-2,232,802; US Serial No. 07/977,442, GB-2,262,831.

45

Several other smectic devices may be made with alignment surfaces of the present invention. For examples electro-clinic smectic devices; mono stable ferro electric devices USP-5,061,047, USP-4,969,719, USP-4,997,264, colour change smectic projection cells USP-5,189,534, GB-2,236,403. The alignment may produce a chevron type C1 or C2 type of smectic micro layer arrangement; or a tilted bookshelf arrangement where rubbing directions on opposite walls are in the same direction, or real bookshelf alignment.

Reducing anchoring energy allows small amounts of translational movement to occur in micro layers formed during cooling from isotropic phases to smectic phases.

Reduction of anchoring energy can be applied to various smectic devices as follows:

(i). Bookshelf and Quasi-bookshelf with low surface viscosity and no surface memory effects

Most materials used in FLC devices exhibit layer shrinkage on cooling through the SmC* phase due to the increase of the angle between the molecules and layer normal on cooling. The tendency for the pinning of the smectic layers at the surfaces then leads to the formation of a chevron structure.

20

25

If the pinning energy is sufficiently high to prevent any translational slippage of the layers (i.e. the energy cost associated with layer slippage is much greater than energies associated with the chevron interface, elastic distortion of the director in the triangular director profile, and the orientational surface energy associated with the director being unable to lie in the preferred alignment direction) the layer shrinking requires that the layers tilt with respect to the surface normal.

If both surfaces have similarly high layer slipping terms then the layers must tilt into a chevron structure which is necessarily symmetric about the central plane of the cell. For typical materials this degree of layer shrinkage is such that the layer tilt angle δ is a constant fraction of the smectic cone angle θ usually about $\delta/\theta = 0.85$. This causes a reduction in the angle between the two bistable states and hence optical contrast in the

46

cell. A higher memory angle may be achieved by lowering δ in what is often termed quasi bookshelf geometry. If the layer pinning term is made sufficiently weak (for example a relatively high concentration of the surfactant is used) a bookshelf geometry is obtained i.e. $\delta=0$. If the azimuthal angle β is also made sufficiently low then a uniform director profile is possible in which the two bistable states are at the optimum angle of $\pm \theta$ to the rubbing direction. The resulting high contrast and brightness of the display is also combined with the other advantages of reduced/no surface memory effects (which would be a problem in other bookshelf devices) and faster response (due to the decoupling of the surface director from the solid surface the surface viscosity becomes equivalent to that of the bulk).

(ii). Chevron with improved memory angle.

This device uses the slippery surfactant at sufficient concentration to lower layer tilt angle in chevron geometry, thereby leading to a higher memory angle and improved brightness for multiplexed devices. However, it may be possible to lower the orientational surface energies without a strong effect on the translation energy (i.e. layer pinning). Thus, the chevron structure would remain to a large extent (i.e. δ remains unchanged) but the orientation of the director at the surface would be higher. For no applied AC field the surface twist of the director would approach that of the chevron interface. The optical uniformity of this state (and hence contrast) would be improved. Moreover, the lowered surface energy would increase the angle of the director at the surface with an applied AC field, and thus the brightness of an AC stabilised display will also be enhanced.

25

30

20

5

10

15

(iii). Improving isotropic to smectic transition.

Surfactant allows layers to slip easily over the surface to form energy state (i.e. uniform layers) dictated by orientational properties of the surface alone (i.e. no translational restrictions). Particularly useful also in AFLC where N* (cholesteric) phase is usually not apparent, but also in other devices (e.g., FLC) where stringent material requirements prevent the use of an N(*) phase.

47

(iv)..Improved stability to mechanical, triennial or electrical damage of smectic devices.

Disruption of a well aligned smectic sample through mechanical, electrical or thermal shock leads to pinning of the layers at the surface which is difficult to remove, even though the disrupted state is not the lowest energy state. It' the pinning is removed then the system may relax back to this minimum energy state before the disruption.

(v)...Improved high tilt chevron device.

10

15

25

High surface pre-tilts are used to ensure that the surface orientation of a FLC device in the chevron geometry approaches the cone angle and hence the memory angle is improved (this is used by CANON and is in Jones, Towler Hughes review). In the unwound N* phase the director has a large degree of splay and bend distortion. On cooling into the smectic A phase this bend cannot be supported, due to the presence of the layers and the distortion is pushed to the surfaces where the director is forced to lie away from the desired pretilt. This may lead to variations in the alignment and hence defects in the SmC* phase (until switched this geometry often forms a "sandy texture" on first cooling). Moreover, there may be a plastic change of the pre-tilt caused by the zenithal surface memory effect. This means that when cooled into the SmC* phase the effective pretilt is lowered and the resulting memory angle is reduced somewhat.

With the slippery surfactant, the surface memory is reduced and the pre-tilt remains unchanged. Note, this is an example where the slippery surface technique is used in the nematic phase, but results in improved performance of a smectic device.

(vi). Improved Electroclinic and antiferroelectric (AFLC) devices

In both of these devices, director twist is induced by the DC electric field there is a tendency for the smectic layers to shrink. If pinned at the surface the applied field tends to induce layer tilt, (although in contradiction to the requirement that E | Pi) which reduces optical appearance through defects, and may also reduce viewing angle

WO 99/18474 PCT/GB98/03011.

48

since the director may tilt out of the cell plane. With the slippery surfactant, both the director and the layers can move easily across the surface, without surface memory or viscosity effects.

5 (viii. Improved N - SmC device.

Advantages ranging from: reduced tendency to form chevron type structure; reduced surface memory; faster surface switching.

10 (viii). Reduced tendency form T state formation in FLC

Due to reduced polar surface interaction. This ensures the good optical and electrooptical properties of any of the above devices (in particular the chevron and bookshelf devices).

15

(ix). Improved alignment of smectic devices.

Treatment prevents defects (for example pitch lines in overlying N* phase, or Cl state/zig-zags in SmC*) from become pinned at surface irregularities.

20

The monomer materials used in embodiments of the invention may include the following, which are given only by way of example:

methyl acrylate	propane-1,3-diol diacrylate
ethyl acrylate	butane-1,4-diol diacrylate
propyl acrylate	pentane-1,5-diol diacrylate
butyl acrylate	hexane-1,6-diol diacrylate
pentyl acrylate	heptane-1,7-diol diacrylate
2-methylbutyl acrylate	octane-1,8-diol diacrylate
hexyl acrylate	nonane-1,9-diol diacrylate
heptyl acrylate	decane-1,10-diol diacrylate
octyl acrylate	glycerol triacrylate
nonyl acrylate	trimethylolpropane triacrylate

pentacrythritol triacrylate decyl acrylate pentaerythritol tetraacrylate ethyl hexyl acrylate methyl methacrylate di-pentaerythritol hexaacrylate ethylene glycol dimethacrylate ethyl methacrylate propyl methacrylate 1,2-propylene glycol dimethacrylate propane-1,3-diol dimethacrylate butyl methacrylate butane-1,4-diol dimethacrylate pentyl methacrylate 2-methylbutyl methacrylate pentane-1,5-diol dimethacrylate hexane-1,6-diol dimethacrylate hexyl methacrylate heptane-1,7-diol dimethacrylate heptyl methacrylate octyl methacrylate octane-1,8-diol dimethacrylate nonane-1,9-diol dimethacrylate nonyl methacrylate decane-1,10-diol dimethacrylate. decyl methacrylate ethyl hexyl methacrylate glycerol trimethacrylate trimethylolpropane trimethacrylate styrene ethylene glycol diacrylate pentaerythritol trimethacrylate pentaerythritol tetramethacrylate 1,2-propylene glycol diacrylate di-pentaerythritol hexamethacrylate

A further class of polymers includes di-thiol/diene polymers prepared by the copolymerisation of difunctional alkenes with difunctional thiols under free radical conditions. Monofunctional and/or polyfunctional alkenes and/or thiols may be incorporated in order to modify the properties of the polymer, for example to reduce the molecular weight of the polymer or to introduce a controlled degree of crosslinking in the polymer. The following materials given by way of example only may be included in polymers suitable for use in embodiments of the invention:

methyl acrylate styrene
ethyl acrylate ethylene glycol diacrylate
propyl acrylate 1,2-propylene glycol diacrylate
butyl acrylate propane-1,3-diol diacrylate
pentyl acrylate butane-1,4-diol diacrylate
2-methylbutyl acrylate pentane-1,5-diol diacrylate

hexyl acrylate heptyl acrylate octyl acrylate nonyl acrylate decyl acrylate ethyl hexyl acrylate methyl methacrylate ethyl methacrylate propyl methacrylate butyl methacrylate pentyl methacrylate 2-methylbutyl methacrylate hexyl methacrylate heptyl methacrylate octyl methacrylate nonyl methacrylate decyl methacrylate ethyl hexyl methacrylate ethylene glycol divinyl ether 1,2-propylene glycol divinyl ether propane-1,3-diol divinyl ether butane-1,4-diol divinyl ether pentane-1,5-diol divinyl ether hexane-1,6-diol divinyl ether heptane-1,7-diol divinyl ether octane-1,8-diol divinyl ether nonane-1,9-diol divinyl ether decane-1,10-diol divinyl ether glycerol trivinyl ether trimethylolpropane trivinyl ether divinyl benzene butane-1,3-diene pentane-1,4-diene

hexane-1,6-diol diacrylate heptane-1,7-diol diacrylate octane-1,8-diol diacrylate nonane-1,9-diol diacrylate decane-1,10-diol diacrylate glycerol triacrylate trimethylolpropane triacrylate pentaerythritol triacrylate pentaerythritol tetraacrylate di-pentaerythritol hexaacrylate ethylene glycol dimethacrylate 1,2-propylene glycol dimethacrylate propane-1,3-diol dimethacrylate butane-1,4-diol dimethacrylate pentane-1,5-diol dimethacrylate hexane-1,6-diol dimethacrylate heptane-1,7-diol dimethacrylate octane-1,8-diol dimethacrylate nonane-1,9-diol dimethacrylate decane-1,10-diol dimethacrylate glycerol trimethacrylate trimethylolpropane trimethacrylate pentaerythritol trimethacrylate pentaerythritol tetramethacrylate di-pentaerythritol hexamethacrylate ethylene glycol diallyl ether 1,2-propylene glycol diallyl ether propane-1,3-diol diallyl ether butane-1,4-diol diallyl ether pentane-1,5-diol diallyl ether hexane-1,6-diol diallyl ether heptane-1,7-diol diallyl ether octane-1,8-diol diallyl ether

nonane-1,9-diol diallyl ether hexane-1,5-diene decane-1,10-diol diallyl ether heptane-1,7-diene glycerol triallyl ether octane-1,7-diene trimethylolpropane triallyl ether nonane-1,8-diene di-allyl malonate decane-1,9-diene di-allyl succinate ethylene glycol dithioglycollate 1,2-propylene glycol dithioglycollate di-allyl glutanate di-allyl hexane-1,6-dicarboxylate propane-1,3-diol dithioglycollate di-allyl keptane-1,7- dicarboxylate butane-1,4-diol dithioglycollate di-allyl octane-1,8- dicarboxylate pentane-1,5-diol dithioglycollate di-allyl nonane-1,9- dicarboxylate hexane-1,6-diol dithioglycollate di-allyl decane-1,10- dicarboxylate heptane-1,7-diol dithioglycollate di-allyl undecane-1,11- dicarboxylate octane-1,8-diol dithioglycollate di-allyl dodecane-1,12- dicarboxylate nonane-1,9-diol dithioglycollate di-allyl phthalate decane-1,10-diol dithioglycollate butane-1,4-diol di-3-mercaptopropionate glycerol trithioglycollate pentane-1,5-diol di-3-mercaptopropionate trimethylolpropane trithioglycollate hexane-1,6-diol di-3-mercaptopropionate pentaerythritol trithioglycollate heptane-1,7-diol di-3-mercaptopropionate pentaerythritol tetrathioglycollate octane-1,8-diol di-3-mercaptopropionate di-pentaerythritol hexathioglycollate nonane-1,9-diol di-3-mercaptopropionate 4,4'-thiobisbenzenethiol decane-1,10-diol di-3-mercaptopropionate di-allyl iso-phthalate glycerol tri-3-mercaptopropionate di-allyl terephthalte trimethylolpropane tri-3-mercaptopropionate ethane dithiol pentaerythritol tri-3-mercaptopropionate propane dithiol pentaerythritol tetra-3-mercaptopropionate butane dithiol hexa-3di-pentaerythritol pentane dithiol mercaptopropionate Also commercial polymers from Norland hexane dithiol and Merck eg Norland 65, Norland 63 and

Merck MXM035

heptane dithiol octane dithiol

52

nonane dithiol

decane dithiol

undecane dithiol

dodecane dithiol

ethylene glycol

di-3-

mercaptopropionate

1,2-propylene glycol

di-3-

mercaptopropionate

propane-1,3-diol

di-3-

mercaptopropionate

Claims:

5

30

1. A liquid crystal device comprising a layer of a liquid crystal material contained between two spaced cell wall carrying electrodes structures and an alignment treatment on at least one wall,

characterised by

means for reducing anchoring energy at the surface alignment on one or both cell walls.

- 2. The device of claim 1 wherein the means for reducing energy is an oligomer or short chain polymer within the liquid crystal material at the cell walls.
- 3. The device of claim 1 wherein the means for reducing energy is an oligomer containing esters, thiols, and/or acrylate monomers within the liquid crystal material at the cell walls.
- 4. The device of claim 2 wherein the oligomer or short chain polymer has imperfectsolubility in the liquid crystal material.
 - 5. The device of claim 2 wherein the oligomer or short chain polymer has a physical affinity for the surface of the cell wall.
- 6. The device of claim 2 wherein the oligomer or short chain polymer retains a substantially liquid like surface at the polymer and liquid crystal material interface
 - 7. The device of claim 2 wherein the oligomer or polymer is substantially non-crystalline within the liquid crystal material.
 - 8. The device of claim 2 wherein the oligomer or polymer reduces the liquid crystal material order parameter at or adjacent the cell walls.

54

- 9. The device of claim 2 wherein the oligomer or polymer changes the phase of the liquid crystal material at or adjacent the cell walls.
- 10. The device of claim 2 wherein the oligomer or polymer has a glass transition temperature below the operating temperature range of the device.
 - 11. The device of claim 2 wherein the oligomer or polymer is substantially linear or includes branch points, either with or without crosslinking.
- 12. The device of claim 2 wherein the oligomer or polymer has a number of repeat units within the range of 4 to 1000.
 - 13. A method of making a liquid crystal device comprising the steps of:-
- providing a layer of a liquid crystal material contained between two spaced cell wall carrying electrodes structures and an alignment treatment on at least one wall,

characterised by

25

- the step of reducing anchoring energy at the surface alignment on one or both cell walls.
 - 14. The method of claim 11 wherein the oligomer or short chain polymer is formed by polymerisation of reactive low molecular weight materials in solution in the liquid crystal fluid.
 - 15. The method of claim 11 wherein the oligomer or short chain polymer is formed by polymerisation of reactive low molecular weight materials in solution in the liquid crystal material prior to its introduction between the cell walls.
 - 16. The method of claim 11 wherein the oligomer or short chain polymer is formed by polymerisation of reactive low molecular weight materials in solution in the liquid crystal material after to its introduction between the cell walls.

5

30

- 17. The method of claim 11 wherein the oligomer or short chain polymer is formed by polymerisation of reactive low molecular weight materials in the presence of an inert solvent which is then removed and the resulting polymer dissolved in the liquid crystal material prior to its introduction between the cell walls.
- 18. A twisted nematic liquid crystal device capable of being switched from a twisted stated to a non twisted state comprising;
- 10 two cell walls enclosing a layer of nematic liquid crystal material;
 - electrode structures on both walls for applying an electric field across the liquid crystal layer;
- a surface alignment on both cell walls providing alignment direction to liquid crystal molecules and arranged so that a twisted nematic structure is formed across the liquid crystal layer;
- means for distinguishing between the two different optical states of the liquid crystal material;

CHARACTERISED BY

- means for reducing zenithal anchoring energy in the surface alignment on one or both cell walls.
 - 19. The device of claim 18 wherein the means for reducing zenithal anchoring energy is an oligomer which is coated onto the inner surface of one or both cell walls either spread on the surface or added to the liquid crystal material.
 - 20. The device of claim 18 wherein the means for reducing and zenithal anchoring energy is an oligomer incorporated in the liquid crystal material.

56

- 21. The device of claim 18 wherein the means for reducing zenithal anchoring energy is N65, or MMXM035.
- 22. The device of claim 18 wherein the means for reducing zenithal anchoring energy is a material containing esters, thiols, and/or acrylate monomers.
 - 23. The device of claim 18 wherein the means for reducing zenithal anchoring energy reduces the liquid crystal material order parameter at or adjacent the cell walls.
- 10 24. The device of claim 18 wherein the means for reducing zenithal anchoring energy changes the phase of the liquid crystal material at or adjacent the cell walls.
 - 25. The device of claim 18 including means for reducing azimthal anchoring energy.
- 26. The device of claim 18 wherein the surface alignment provides a pretilted nematic alignment on both cell walls.
 - 27. The device of claim 18 wherein the surface alignment is provided by a rubbed polymer, a photo-ordered polymer or an obliquely evaporated inorganic material.
 - 28. The device of claim 18 wherein the surface alignment layer is a surface monograting with an asymmetric groove profile.

- 29. The device of claim 18 wherein the alignment directions on the two surface are substantially perpendicular.
 - 30. The device of claim 18 wherein the liquid crystal director twists by about 90° throughout the thickness of the cell.
- 31. The device of claim 18 wherein the liquid crystal director twists is greater than 180° and less than 360°.

57

32. The device of claim 18 wherein the nematic liquid crystal material contains a small amount (<5%) of a chiral dopant material.

33. A bistable nematic liquid crystal device capable of being switched into two
 5 different stable states comprising

two cell walls enclosing a layer of nematic liquid crystal material;

electrode structures on both walls;

10

a surface alignment on one or both cell walls providing two alignment directions to liquid crystal molecules with an amount of surface pretilt;

means for distinguishing between switched states of the liquid crystal material;

15

CHARACTERISED BY

means for reducing inelastic azimuthal memory anchoring energy in the surface alignment on one or both cell walls.

- 34. The device of claim 33 and including means for reducing zenithal anchoring energy
- 35. The device of claim 33 wherein the means for reducing the anchoring energy is an oligomer or short chain polymer which is either spread on the surface or added to the liquid crystal material.
 - 36. The device of claim 35 wherein the oligomer is a material selected from:
- 30 Norland N65

$$-[S(CH2)6S CH2CH2O(CH2)6O CH2CH2]n - CH2 = CH O(CH2)6O CH=CH2 HDVE (Hexane -1,6-diol di(vinyl ether))$$

58

CH2 = CHOC4H9

BVE (Butyl vinyl ether)

HSCH₂CO₂(CH₂)₂OCOCH S₂H

EGTG (Ethylene glycol bis(thioglycollate))

HS(CH₂)₉SH

NDT (Nonane-1,9-dithiol)

37. The device of claim 35 wherein the oligomer is an amount up to 10.% by weight in the liquid crystal material.

- 38. The device of claim 35 wherein the chain length (n) is less than 100 repeat units.
- 39. The device of claim 35 wherein the oligomer's parameters of type, concentration, chain length, are arranged to reduce the liquid crystal order parameter at or adjacent the cell wall.
- 40. The device of claim 35 wherein the ologomer's parameters of type, concentration, chain length, are arranged to change the phase of the liquid crystal material at or adjacent the cell wall.
 - 41. The device of claim 35 wherein the oligomer is a material is a material that has been precured prior to introduction between the cell walls.

20

- 42. The device of claim 35 wherein the oligomer is a material that has been precured after introduction between the cell walls.
- 43. The device of claim 33 wherein the surface alignment is provided by a bigrating surface.
 - 44. A smectic liquid crystal device comprising:
- a liquid crystal cell including a layer of smectic liquid crystal material contained between two walls bearing electrodes and surface treated to give both an alignment and a surface tilt to liquid crystal molecules;

CHARACTERISED BY

10

20

means for reducing anchoring energy at the surface alignment on one or both cell walls.

- 5 45. The device of claim 44 wherein the means for reducing energy is an oligomer or short chain polymer within the liquid crystal material at the cell walls.
 - 46. The device of claim 44 wherein the means for reducing energy is an oligomer containing esters, thiols, and/or acrylate monomers within the liquid crystal material at the cell walls.
 - 47. The device of claim 45 wherein the oligomer or short chain polymer has imperfect solubility in the liquid crystal material.
- 15 48. The device of claim 45 wherein the oligomer or short chain polymer has a physical affinity for the surface of the cell wall.
 - 49. The device of claim 45 wherein the oligomer or short chain polymer retains a substantially liquid like surface at the polymer and liquid crystal material interface
 - 50. The device of claim 45 wherein the oligomer or polymer is substantially noncrystalline within the liquid crystal material.
- 51. The device of claim 44 wherein the oligomer or polymer reduces the liquid crystal material order parameter at or adjacent the cell walls.
 - 52. The device of claim 44 wherein the oligomer or polymer changes the phase of the liquid crystal material at or adjacent the cell walls.
- 53. The device of claim 44 wherein the liquid crystal material is a chiral smectic material, the alignment directions on the two cell walls are substantially parallel, and the device is a bistable device.

- 60
- 54. The device of claim 44 wherein the alignment directions on the two cell walls are non parallel.
- 55. The device of claim 44 wherein the liquid crystal material is a non-chiral smectic5 material.
 - 56. The device of claim 44 wherein the liquid crystal material is a smectic A material.
 - 57. The device of claim 44 wherein the alignment is provided by a grating surface.

- 58. The device of claim 44 wherein the alignment is provided by a rubbed polymer surface.
- 59. The device of claim 44 wherein one cell wall has an alignment treatment, the other cell wall has no azimuthal alignment direction, and both cell walls are treated with the means for reducing anchoring energy.

1/10






Fig. 1



SUBSTITUTE SHEET (RULE 26)






Fig. 5







Fig. 6


SUBSTITUTE SHEET (RULE 26)






SUBSTITUTE SHEET (RULE 26)





SUBSTITUTE SHEET (RULE 26)



SUBSTITUTE SHEET (RULE 26)






Fig. 13





SUBSTITUTE SHEET (RULE 26)






Fig. 16





Fig. 17

SUBSTITUTE SHEET (RULE 26)

10/10



SUBSTITUTE SHEET (RULE 26)

INTERNATIONAL SEARCH REPORT

Interr Ind Application No PCT/GB 98/03011

	SIFICATION OF SUBJECT MATTER G02F1/1337			
According	to International Patent Classification (IPC) or to both national class	ification and IPC		
8. FIELD	S SEARCHED			
IPC 6				
	tation searched other than minimum documentation to the extent the			
2.0Crons	data base consulted during the international search (name of data	Dase and, where practical, search terms used	a)	
C. DOCUI	MENTS CONSIDERED TO BE RELEVANT			
Category	Citation of document, with indication, where appropriate, of the	relevant passages	Relevant to claim No.	
X	GB 2 286 893 A (SECR DEFENCE) 30 August 1995 cited in the application see page 1, paragraph 2 - paragr	1,13,18, 19, 23-32, 44,54,57		
	see page 1, paragraph 2 paragraph 5 see page 4, paragraph 11 see page 6, paragraph 5 see page 9, paragraph 3 * Abstract *	αρπ 3		
X	GB 2 286 466 A (SECR DEFENCE) 16 August 1995 cited in the application see page 1, paragraph 1 - paragraph 3 see page 6, paragraph 3 see page 7, paragraph 3 * Abstract *	raph 3	1,13,18, 19,23-32	
 		-/		
X Fut	ther documents are listed in the continuation of box C.	X Patent family members are listed	in ernex.	
"A" docume consider of filing of "L" docume which citatio "O" docume other of the country of the	ent defining the general state of the art which is not dered to be of particular relevance document but published on or after the international date ent which may throw doubts on priority claim(s) or is cited to establish the publication date of another in or other special reason (as specified) sent referring to an oral disclosure, use, exhibition or means ent published prior to the international filing date but hen the priority date claimed	"I" later document published after the international filing date or priority date and not in conflict with the application but cited to understand the principle or theory underlying the invention "X" document of particular relevance; the claimed invention cannot be considered novel or cannot be considered to involve an inventive step when the document is taken alone "Y" document of particular relevance; the claimed invention cannot be considered to involve an inventive step when the document is combined with one or more other such documents, such combination being obvious to a person skilled in the art. "&" document member of the same patent tamily		
Date of the	actual completion of the international search	Date of mailing of the international sea		
1	8 December 1998	04/01/1999		
Name and n	Talling address of the ISA European Patent Office, P.B. 5818 Patentiann 2 NL - 2280 HV Rijswijk Tel 4-21-70 240-2040 Tr. 21-551 and of	Authorized officer		
	Tel. (+31-70) 340-2040, Tx. 31 651 epo nl, Facc (+31-70) 340-3018	Petitpierre, O		

INTERNATIONAL SEARCH REPORT ·

Inter: ::al Application No PCT/GB 98/03011

		PCT/GB 98/03011	
	ation) DOCUMENTS CONSIDERED TO BE RELEVANT		
Category *	Citation of document, with indication, where appropriate, of the relevant passages	Refevant to claim No.	
X	US 5 040 876 A (PATEL JAYANTILAL S ET AL) 20 August 1991 see column 1, line 67 - column 2, line 2 see column 2, line 18 - line 26 see column 2, line 65 - column 3, line 18 see column 3, line 19 - line 38 see column 3, line 50 - line 56	1,18, 23-32	
	us 4 577 930 A (YANG KEI-HSIUNG) 25 March 1986 see column 1, line 25 - line 33 see column 3, line 1 - line 15 see column 3, line 65 - line 68 see column 6, line 4 - line 8 see column 6, line 56 - line 67	1,13,18, 19, 23-35, 39,40,43	
	•		

INTERNATIONAL SEARCH REPORT

...ormation on patent family members

Intern at Application No PCT/GB 98/03011

Patent document cited in search repo		Publication date		Patent family member(s)	Publication date
GB 2286893	A	30-08-1995	CA	2182964 A	17-08-1995
			CN	1145120 A	12-03-1997
			DE	69501395 D	12-02-1998
			DE	69501395 T	16-04-1998
			EP	0744039 A	27-11-1996
			ES	2111392 T	01-03-1998
			WO	9522075 A	17-08-1995
			GB	2301447 A	04-12-1996
		•	JP	9508714 T	02-09-1997
			US	5724113 A	03-03-1998
GB 2286466	A	16-08-1995	CA	2182963 A	17_00_1005
		40 00 4550	CN	1145119 A	17-08-1995
			DE	69500923 D	12-03-1997 27-11-1997
			DE	69500923 T	05-03-1998
			EP	0744042 A	27-11-1996
			Ë\$	2108569 T	16-12-1997
			MO	9522078 A	17-08-1995
		•	GB	2301448 A	04-12-1996
			JP	9508717 T	02-09-1997
			SG	47941 A	17-04-1998
			ÜS	5764325 A	09-06-1998
US 5040876	Α	20-08-1991	CA	2022127 A	08-09-1991
			WO	9114200 A	19-09-1991
US 4577930	A	25-03-1986	EP	0095012 A	30-11-1983
			JP	1728142 C	19-01-1993
			JP	4015926 B	19-01-1993
			JP	58209717 A	06-12-1983